


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County. Sec. 27 Twp. 21S Rge. 12W (E)XXXXXX(W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE
Lease Owner Anschutz Drilling Company, Inc.
Lease Name Wilson Well No. 1
Office Address 709 Union Nat'l Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8/26 19 50
Application for plugging filed 8/26 19 50
Application for plugging approved 8/26 19 50
Plugging commenced 8/26 19 50
Plugging completed 8/26 19 50
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3685 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8/5/8"	309'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug set at 307' with 15 sacks cement.
Top plug set at 30' with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anschutz Drilling Company, Inc.
Address 709 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
M. W. Smith (employee of owner) of (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

SUBSCRIBED AND SWORN to before me this 30th day of August, 19 50

Patricia Meeker, Notary Public.

My commission expires Jan. 21, 1954.

PLUGGING
FILE SEC 27 T 21 R 12W
BOOK PAGE 24 LINE 15

AUG 31 1950 8-31-50

DRILLER'S LOG

ANSCHUTZ DRILLING COMPANY, INC.
 #1 Wilson
 NE NE NE - SECTION 27-21S-12W
 STAFFORD COUNTY, KANSAS

0	40	Surface clay & sand
40	205	Sand
205	333	Red bed & sand streak
333	605	Red bed & shells
605	630	Anhydrite
630	960	Shale & shells
960	1330	Shale, shells & salt
1330	1500	Shale & shells
1500	1525	Lime
1525	1675	Lime
1675	1720	Lime
1720	1790	Shale & broken lime
1790	1880	Sandy lime
1880	1945	Broken lime & shale
1945	2070	Lime & shale
2070	2215	Shale & shells
2215	2245	Shale & shells
2245	2310	Lime
2310	2395	Shale & Lime
2395	2540	Shale & lime
2540	2650	Shale & shells
2650	2770	Shale & shells
2770	2895	Lime & shale
2895	2995	Shale & Lime
2995	3060	Lime
3060	3114	Lime
3114	3180	Lime & shale
3180	3275	Shale & shells
3275	3322	Lime
3322	3365	Lime
3365	3490	Lime
3490	3530	Lime & shale
3530	3572	Lime, chert, & shale
3572	3598	Shale & lime
3598	3600	Conglomerate
3600	3637	Arbuckle & shale
3637	3650	Lime & shale
3650	3685	Lime
3685		ROTARY TOTAL DEPTH

COMMENCED: 8/15/50
 COMPLETED: 8/25/50

CASING RECORD:

Set 8-5/8" surface casing
 at 309' with 225 sacks cement
 and 2 CC

D & A

TOPS:

Hebner	3116	
Br. Lime	3249	
K. C.	3254	(-1407)
Cong.	3506	(-1659)
Viola	3536	
Simp. Sh.	3561	
Rew. Arb.	3600	
Sol. Arb.	3655	
T. D.	3685	

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Wilson located in the NE NE NE of Section 27-21S-12W, Stafford County, Kansas

ANSCHUTZ DRILLING CO., INC.

BY: *M. W. Smith*
 M. W. Smith

Subscribed and sworn to before me this 30th day of August, 1950.

Laura Neuber
 Notary Public

My commission expires January 21, 1954.

PLUGGING
 FILE SEC 27-T 21 R 12W
 BOOK PAGE 26 LINE 15