

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-185-21.158-00-01

1 S. Market, Room 2078
Wichita, KS 67202

RECEIVED
APR 24 2002
4-24-02
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Shumway

WELL NUMBER 3

990 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 27 TWP. 21 RGE. 12W (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 3-26-02

Plugging Completed 3-28-02

LEASE OPERATOR L.D. Drilling, Inc.

DRESS R.R. 1 Box 183B Great Bend, Kansas 67530

PHONE (620) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well oil EOR

(Oil, Gas, D&A, SMO, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

Richard Lacey (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 3650'

Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	333'	None
				4-1/2"	3633'	2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each side. Plugged off bottom with sand to 3290' and 4 sacks cement. Shot pipe @2600' and 2400', pulled up to 660', pumped 10 sacks gel and 50 sacks cement, pulled up to 360', pumped 50 sacks cement, pulled up to 40' and circulated 30 sacks cement, 60/40 pos. 10% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L.D. Drilling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of April, 2002

Irene Herzberg
Notary Public

My Commission Expires: _____



OR

DRILLERS WELL LOG

L. D. DRILLING, INC. - CONTRACTOR

L. D. DAVIS - OPERATOR

SHUMWAY # 3
NE-SW-SE
Sec. 27-21-12
Stafford County, Kansas

T.D. 3650'
Elev. 1845' K.B.

COMMENCED: 11-10-80
COMPLETED: 11-18-80

CASING:

8-5/8" set at 333'
4 1/2" set at 3633'

CEMENT:

W/255 sk. 50/50 Pozmix, 2% Gel, 3% C
W/175 sx. 50/50 Pozmix, 18% Salt Sat
3/4 CFR 2

FORMATION

Sand
Red Bed
Anhy.
Shale & shells
Shale & Lime
Lime W/shale
R.T.D.

DEPTH

0 - 474
474 - 630
630 - 656
656 - 1935
1935 - 2265
2265 - 3650
3650

TOPS:

Anhy.
Howard
Severe
Topeka
Heebner
Toronto
Douglas
B. Lime
Lansing K/C
Base K/C
Cong. Shale
R.T.D.

Sample

630-656
2740
2793
2819
3124
3141
3155
3255
3276
3499
3651

Log

623-647
2740
2793
2829
3121
3140
3153
3256
3274
3501
3536
Log T.D. 3651

STATE OF KANSAS)
COUNTY OF BARTON) ss

RECEIVED
MAR 15 2002

I certify that this is a true and correct copy of the above log to the best of my knowledge. KCC WICHITA

L. D. DRILLING, INC.

Don Popp
Don Popp

Sworn to and subscribed before me this 20th day of November, 1980.

My appointment expires: 5-20-81

Bessie M. DeWerff
Bessie M. DeWerff, Notary Public

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81