

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-185-01901-00-01

API NUMBER Drilled 11/43

LEASE NAME WELSH

WELL NUMBER #1-A

2330 Ft. from (S) Section Line

330 Ft. from (W) Section Line

SEC. 18 TWP. 21 RGE. 12 (E) or (W)

COUNTY STAFFORD

Date Well Completed 11/43

Plugging Commenced 3-16-98

Plugging Completed 3-16-98

RECEIVED  
 KANSAS CORP  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.  
 3-31-98  
 1998 MAR 31 1:15

LEASE OPERATOR XANADU EXPLORATION CO.

ADDRESS 6 East. Fifth, Ste. 200 Tulsa, Ok. 74103

PHONE# (918) 584-3802 OPERATORS LICENSE NO. 31798

Character of Well SWD EOR Pvt KCC per Lic Docket  
4/11/08 E.06117

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 16, 1998 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? well drilled 11/43

Producing Formation K/C & Arbuckle Depth to Top \_\_\_\_\_ Bottom T.D. 3720'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface		0	285	10 3/4"	285	none
production		0	3554	5 1/2"	3554	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

Mixed 50 sx. Down backside Max Pressure 400# Shut in 100# Hooked to 5 1/2" csg and mixed  
300# hulls 25 sx. cwmwnt, 22 sk gel spacer, 115 sx. cement Max press 400# shut in 50#  
TOTAL: 190 sx. 60/40 Poz. 6% Gel, 22 gel, 300# hulls Plug down 12:00 P.M. 3-16-98  
 ALLIED CEMENTING COMPANY

Name of Plugging Contractor ALLIED CEMENTING License No. \_\_\_\_\_

Address P.O. BOX 31 RUSSELL, KANSAS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: XANADU EXPLORATION COMPANY

STATE OF KANSAS COUNTY OF BARTON, ss.

Mike Kasselmann (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Mike Kasselmann

(Address) R.R. 1 Box 183 B Great Bend, Ks.  
 67530

SUBSCRIBED AND SWORN TO before me this 24th day of March, 19 98

Bessie M. DeWerff  
 Notary Public  
 Bessie M. DeWerff

My Commission Expires: 5-20-2001

NOTARY PUBLIC - State of Kansas  
 BESSIE M. DeWERFF  
 My Appt. Exp. 5-20-2001