

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 18 Twp. 21 Rge. 12 (E)      (W)

Location as "NE/CNW/SW" or footage from lines SE NE NE

Lease Owner L. K. Parrish

Lease Name Christiansen Well No. #2

Office Address Fourth National Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed December 30 19 63

Application for plugging filed December 30 19 63

Application for plugging approved December 30 19 63


Plugging commenced December 30 19 63

Plugging completed December 30 19 63

Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production      19     

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas

Producing formation      Depth to top      Bottom      Total Depth of Well 3613 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	249.94'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Filled hole with heavy mud to 240'.  
Set plug. Put in 25 sacks cement.  
Filled with heavy mud up to 40'.  
Set plug. Filled to top with 1/2  
sack hulls and 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 13 1964  
1-13-64  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.

Address 107 Rule Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
G. F. Galloway (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway

107 Rule Building  
(Address)

Subscribed and sworn to before me this 30 day of December, 19 63

Vicky Jacobs  
Notary Public.



W E L L L O G

OPERATOR L. K. Parrish SEC. 18-21-12  
 WELL NAME Christiansen #2 LOC. SE NE NE  
 TOTAL DEPTH 3613' COUNTY Stafford  
 COMM. 12/17/63 COMP. 12/30/63 STATE Kansas  
 RIG NO. # 2 ELEVATION 1863 K.B.  
 CASING: Set 249.94' (8 jts,) 8-5/8" OD Surface Casing. PRODUCTION: D & A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	225	Sand		
225	250	Shale		
250	675	Red Bed		
675	705	Anhydrite		
705	1545	Shale Shells	1000' - 0°	
1545	2875	Shale-Lime	2500' - 0°	
2875	3170	Lime	3000' - 0°	
3170	3260	Lime-Shale		DST #1 3276-97
3260	3604	Lime	3500' - 0°	DST #2 3374-91
3604	3613	Conglomerate		

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 13 1964  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 COUNTY OF SEDGWICK ) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway  
 G. F. Galloway  
 THIS 2<sup>nd</sup> day of January, 1964.

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 2<sup>nd</sup> day of January, 1964.

My commission expires:  
 May 20, 1963

Vicky Jacobs  
 Vicky Jacobs - Notary Public

