

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford

County, Sec. 18 Twp. 21 Rge. 12 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE/4 NW/4 SE/4

Lease Owner Midstates Oil Corporation

Lease Name Cora Clark Well No. 8

Office Address 518 Nat'l. Bank of Tulsa Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 29 19 51

Application for plugging filed March 29 (verbal) 19 51

Application for plugging approved March 29 19 51


Plugging commenced March 29 19 51

Plugging completed March 29 19 51

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3695 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	278	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud to bottom of surface casing at 278', Wood plug set in bottom of surface casing, 15 sacks of cement mixed and poured on top of wood plug. Hole filled with mud to 30' of top of surface casing, wood plug set at this point and 10 sacks of cement mixed and poured in filling surface casing to top.

RECEIVED
STATE CORPORATION COMMISSION
APR 12 1951
CONSERVATION DIV.
Wichita, Kansas
4-12-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Midstates Oil Corporation, Attention: Mr. Geo. Address: Mr. Vandaveer, Jr., 518 Nat'l. Bank of Tulsa Bldg., Tulsa 3, Oklahoma.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

Geo. M. Vandaveer, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

Vice President

(Signature) *Geo. M. Vandaveer, Jr.*

518 Nat'l. Bank of Tulsa Bldg., Tulsa 3, Okla. (Address)

SUBSCRIBED AND SWORN to before me this 4th day of April, 19 51

My commission expires February 10, 1955

22-7877-8 4-49-10M

Dorothy H. Torbett
Notary Public

SEE WELL RECORD ON BACK:

DOROTHY H. TORBETT, Notary Public
in and for Tulsa County, Oklahoma
My commission expires February 10, 1955.

PLUGGING
FILE SEC 18 T 21 R 12
BOOK PAGE 71 LINE 6

FORMATION RECORD

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>
0	50	Sand, Clay
50	278	Sand, shale
278	1630	Shale, shells
1630	1730	Lime, shale
1730	1820	Lime
1820	1980	Lime, shale
1980	2045	Lime
2045	2210	Lime, shale
2210	2325	Shale, shells
2325	2607	Lime, shale
2607	2756	Shale
2756	2821	Lime
2821	3169	Lime, shale
3169	3211	Shale
3211	3330	Lime, shale
3330	3530	Lime
3530	3602	Lime, shale
3602	3650	Simpson Lime
3650	3665	Simpson Lime
3665	3695	Arbuckle Lime
Total Depth	3695	

CORPORATION COMMISSION OF

KANSAS

WELL RECORD

PRODUCER: Midstates Oil Corporation

ADDRESS: 518 National Bank of Tulsa Bldg., Tulsa 3, Oklahoma

FARM NAME: Cora Clark WELL NUMBER: Eight

WELL LOCATED: NE NW SE Section 18-21-12W, Stafford County, Kansas

DRILLING COMMENCED: March 11, 1951 DRILLING COMPLETED: March 29, 1951

CASING RECORD

<u>Size</u>	<u>Set</u>	<u>No. Sacks of Cement</u>
8/5/8"	278'	225 sacks

FORMATION RECORD

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>
0	50	Sand, clay
50	278	Sand, shale
278	1630	Shale, shells
1630	1730	Lime, shale
1730	1820	Lime
1820	1980	Lime, shale
1980	2045	Lime
2045	2210	Lime, shale
2210	2325	Shale, shells
2325	2607	Lime, shale
2607	2756	Shale
2756	2821	Lime
2821	3169	Shale, lime
3169	3211	Shale
3211	3330	Lime, shale
3330	3530	Lime
3530	3602	Lime, shale
3602	3650	Simpson Lime
3650	3665	Simpson Lime
3665	3695	Arbuckle Lime
Total Depth	3695	

Status: Dry Hole

PLUGGING
 FILE SEC 18-T-21-R(2)
 BOOK PAGE 71 LINE 6

RECEIVED
 STATE CORPORATION COMMISSION
 APR 12 1951
 CONSERVATION DIVISION
 Wichita, Kansas