

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15.185.13075.0001  
API NUMBER Drilled 08-19-45  
LEASE NAME William McCrary A

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1  
330 Ft. from S Section Line  
660 Ft. from E Section Line

LEASE OPERATOR L.D. Drilling, Inc.  
ADDRESS RR 1 Box 183 B Great Bend, KS 67530

SEC. 19 TWP. 21 RGE. 12 (E) or (W)  
COUNTY Stafford

PHONE (316) 793-3051 OPERATORS LICENSE NO. 6039

Date Well Completed \_\_\_\_\_

Character of Well SWD

Plugging Commenced 02-16-98

(Oil, Gas, P&A, SWD, Input, Water Supply Well)

Plugging Completed 02-16-98

The plugging proposal was approved on 02-16-98 (date)

by Richard Lacey (XCC District Agent's Name)

Is ACO-1 filled? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top 3336' Bottom 3474' T.O. 3578'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content Surface	From -0-	To 280'	Size 10 3/4"	Put In 280'	Pulled out - 0 -
	Production	-0-	5375'	7"	3575'	660'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug vems used, state the character of same and depth placed, - from feet to feet each set  
Bottom plug sand & cement to 3286'. Allied loaded hole, mixed 15 sacks gel 6% spacer followed by 75 sacks cement 60/40% 6% gel - 5 sacks gel to displace at 625'. Pulled casing to 300' and spotted 75 sacks cement, circulated. Pulled casing & topped with 15 sacks cement.  
Job started 11:45 a.m. and completed 2:15 p.m..

Name of Plugging Contractor DS&W Well Servicing, Inc. License No. 6901

Address P.O. Box 231 Claflin, KS 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L.D. Drilling, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Arthur P. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed: the same are true and correct, so help me God.

(Signature) Arthur P. Strube

(Address) P.O. Box 231 Claflin, KS 67525

SUBSCRIBED AND SWORN TO before me this 24th day of February, 19 98

Brenda Urban  
Notary Public

My Commission Expires: Nov 14, 2001

USE ONLY ONE SIDE OF EACH FORM

BRENDA URBAN  
Notary Public - State of Kansas  
My Appt. Expires Nov 14, 2001

CONSERVATION DIVISION Form CP-4  
Wichita, Kansas Revised 05-88