

STATE OF KANSAS  
ATE CORPORATION COMMISSION  
3 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

15-185-13068-00-00  
API NUMBER Dilled 10-1-44

LEASE NAME E.B. Hall  
WELL NUMBER 1

RECEIVED  
NOV 15 2001  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

330 Ft. from N Section Line  
330 Ft. from W Section Line

LEASE OPERATOR BERENERGY CORPORATION  
ADDRESS 3333 S. Wadsworth Blvd. #218 Lakewood, CO. 80227  
PHONE (303) 969-9610 OPERATORS LICENSE NO. 4967

SEC. 19 TWP. 21S RGE. 12W (E) or (W)

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed \_\_\_\_\_  
Plugging Commenced 11-5-01  
Plugging Completed 11-7-01

The plugging proposal was approved on \_\_\_\_\_ (date)  
by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_  
Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3597'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	266'	None
				5-1/2"	3583'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section.  
Set PB @3200', perforated well @700', dumped 2 sacks cement on top of PB. Ran 700' of 2-3/8" tubing, pumped 350 sks. cement, got circulation up 5-1/2" and 8-5/8". Pumped 110 sks. cement and circulated to surface. Layed down tubing, topped off with 65 sacks cement. Cement down 107', pumped 10 sks. down 5-1/2" and 10 sks. down 8-5/8". 60/40 pos, 6% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529  
Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Berenergy Corporation  
State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 12th day of November, 2001

[Signature]  
Notary Public

My Commission Expires:



Form CP  
Revised 05-