

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 1966
1-3-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John J. Darrah

Complete Address: 200 North Main, Wichita, Kansas

Lease Name Asher Well No. # 1

Location SE SW SE Sec. 4 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3505'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 1:15PM Day 29th Month Dec. Year 1966

The Above well was plugged as follows:

367' of 8 5/8" surface pipe, cemented with 275 sacks. 3504' of 5 1/2" long
string, cemented with 100 sacks. Plug back T.D. 2641'. Top perferation
2612'. Bottom of the hole was sanded to 2600', and cemented with 5 sacks,
through the dump bailer. Pipe had been shot of at 2641', and squeezed with
cement from top to bottom. 320' of 5 1/2" long string was recovered from the
hole. Surface pipe was squeezed with 10 sacks of Gel-Mud and 80 sacks of
cement, through an 8 5/8" swage, to a pressure of 100 lbs. A wiping plug
was run between the mud and the cement, the cement was brought to the base
of the cellar. This cementing was done by Globe Cementing Comapny.
I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/3/67
INV. NO. 4537-W

Signed: Archie Elving
Well Plugging Supervisor