

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JUN 28 1978

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas

API Number 15-185-20635.0000 (of this well)

Operator's Full Name Commercial Oil Co. Inc.

Complete Address 5252 N. Broadway Wichita, Kan. 67219

Lease Name Asker Well No. 1

Location SW-SW-SE- Sec. 4 Twp. 25 Rge. 14 (E) (W) X

County Stafford Total Depth 3616

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Art Lamb Casing Pulling Inc.

Address 2809 King St. Hutchinson, Mo. 67501 License No. 440

Operation Completed: Hour 10:15 Am Day 26 Month 6 Year 1978

The above well was plugged as follows:

311'-8 5/8" Casing w/ 200 sac Cement - 5 1/2" Casing set @ 3558'
w/ 100 sac Cement - Top prof. 3436' - push plug to 3430'
Sand back to 3400' - sand topped w/ 5 sac mixed Cement w/
dump bails - pull 2776' 5 1/2" Casing - mix & pump
4 sac shells - 20 sac gel - release plug - mix & pump 125
sac Cement to top of Casing - shut in w/ 300# pressure

Dumped By Sun Cementing Co. St. Bend, Kans. - 67530

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. W. Owen
Well Plugging Supervisor

DATE 6-28-78

INV. NO. 7589.0