

15.185.13003.0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 13 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Frank J. Black

Complete Address: Box 150, McPherson, Kansas

Lease Name Langer Well No. # 2

Location NE NE NE Sec. 4 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3567'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 4:00PM Day 7th Month June Year 1966

The Above well was plugged as follows:

807' of 8 5/8" surface pipe, cemented with 500 sacks. 3563' of 5 1/2" long
string, cemented with 50 sacks. This is an open hole. Bottom of the hole
was sanded to 3550', and cemented with 5 sacks, through the dump bailer.
3060' of 5 1/2" long string was recovered from the hole. Hole was filled
with mud to 300', rock bridge from 300' to 290', and cemented with 25
sacks. Hole was filled with mud to 40', rock bridge from 40' to 30',
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Arlene Elving
Well Plugging Supervisor

INVOICED

DATE 6-13-66

INV. NO. 3388-W