

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-185-21,665 *[Signature]*

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Alpine Drilling Co. Inc. #5040

Complete Address 200 E. 1st Wichita, Kansas 67202

Lease Name Rehn Well No. 1

Location 50'E. of C SE-NE-NW Sec. 10 Twp. 21 Rge. 14 (East)(West)

County Stafford Total Depth 3705'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor J. W. Drilling Inc #5-137 tag 394

Address 200 E 1st Suite 500 Wichita, Kans 67202 License No. _____

Operation Completed: Hour: 3:00 PM Day: 22 Month: 9 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The elevation is 1926 Ground level. The anhydrite was typed at 819'. 1st plug at 840' with 35 lbs of cement. 2nd plug at 360' with 40 lbs of cement. 3rd plug 40' to 0' on solid bridge with 10 lbs of cement. Then circulated 10 lbs of cement in rat hole. Then plugged water well with 3 lbs of cement. The main hole was plugged through drill pipe with hole full of heavy mud. The plugging was accomplished by Sun Cementing.

Amount of Surface Casing: 358' of 8 5/8" K. B. cement circulated with 300 lbs of Common Cement 2% gel 3% cc

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

STATE CORPORATION COMMISSION
RECEIVED
SEP 27 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 10-18-82

INV. NO. 1368-W