

State of Kansas



FORM - CP-2
Rev. 9-8-64

15.185.30050.0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 8 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Doug Boyd of Leben Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Boyd guarantees payment of the plugging fee.

Operator's full Name: Kaiser-Francis

Complete Address: 909 Palace Bldg., Tulsa, Oklahoma 74103

Lease Name: Christiansen "B" Well No. # 1

Location: C E/2 E/2 NW Sec. 18 Twp. 21 Rge. 12(E)(W) W

County Stafford Total Depth 3580' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Boyd was instructed to plug the well as follows:

270' of 8 5/8" surface pipe, cemented with 225 sacks. Fill hole with drilling mud to 260', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent