

State of Kansas



15.185.11353.0000 FORM - CP-2

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 18 1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Earl Dunlap of C-G Drilling Co. has this

date requested permission to plug the following described well:

Mr. Dunlap guarantees payment of the plugging fee.

Operator's full Name: L. K. Parrish

Complete Address: 714 4th National Bank, Wichita, Kansas

Lease Name: Christainsen Well No. # 1

Location: NE NW NW Sec. 18 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3625 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Dunlap was instructed to plug the well as follows:

362' of 8 5/8" surface pipe, cemented with 250 sacks.

Fill hole with mud to 275', 1st cementing plug, 1/2 sack

hulls, cement with 20 sacks. Fill hole with mud to 40',

2nd cementing plug, 1/2 sack hulls, cement with 10 sacks

to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent