



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1966

CONSERVATION DIVISION
WICHITA, KANSAS

11-1-66

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. E. L. Bearden of Shell Oil Company has this

date requested permission to plug the following described well:

Mr. Shell Oil Company guarantees payment of the plugging fee.

Operator's full Name: Shell Oil Company

Complete Address: 1200 1st. Nat'l. Bldg., Oklahoma City, Oklahoma

Lease Name: Bitter "C" Well No. # 3

Location: NE NE SW Sec. 5 Twp. 16 Rge. 13 (E)(W) W

County Barton Total Depth 3368 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. D. B. Pully was instructed to plug the well as follows:

8 5/8" 645' Cwc.

Sanded hole back to 3350' & dumped 4 sax cement with dump bailer.

Pulled pipe. Mudded hole to 370', set 20' rock bridge, & displaced

5 yds. ready-mix cement, cementing from 350' to base of cellar.

Very truly yours,

Don Brian
Conservation Division Agent