



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 4 1964
11-4-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ted L. Nutt of Santa Fe Pipe & Supply has this date requested permission to plug the following described well:

Mr. Ted L. Nutt guarantees payment of the plugging fee.

Operator's full Name: Santa Fe Pipe & Supply Inc.

Complete Address: Box 562, Great Bend, Kansas

Lease Name: Bitter Well No. # 1

Location: G S/2 NW Sec. 5 Twp. 16 Rge. 13 (E) (W) W

County Barton Total Depth 3344 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Russell Hoberrecht was instructed to plug the well as follows:

8 5/8" 337' Gwc.

Sanded hole back to 3330' & dumped 4 sax cement with
dump bailer. Pulled pipe. Mudded hole to 320'; set rock
bridge; displaced 25 sax cement. Mud to 40'; set rock
bridge; displaced 10 sax cement, cementing to base of
cellar.

Very truly yours,

Don Truman
Conservation Division Agent