

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1978

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 113-20470.0000 (of this well)

Operator's Full Name Barnett Oil, Inc.
Complete Address 1625 Vickers-KSB&T Bldg, 125 N. Market, Wichita, Ks.
Lease Name Cra 66 Well No. 1
Location C N/2 NW Sec. 30 Twp. 21 Rge. 2 (E) (W)X
County McPherson Total Depth 3255
Abandoned Oil Well Gas Well X Input Well SWD Well D & A
Other well as hereafter indicated

Plugging Contractor Mark Hurst
Address 2400 N. Main, Hutchinson, Kansas License No. 821

Operation Completed: Hour 11 AM Day 28 Month December Year 1978

The above well was plugged as follows: 8 3/8" - 192' cement circ. 4 1/2" - 3254-50 sacks
4 1/2" plug pushed to 3100'. Hole filled with sand to 3090' and
cemented with 3 sacks. Hole filled with mud to 280'. Rock
bridge set to 180' and cemented with 25 sacks cement.
Hole filled with mud to 40'. Rock bridge set from 40' to 30'
and hole cemented to base of cellar with 10 sacks
cement.
2200' of 4 1/2" casing recovered

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 1-3-79
8874.W