

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE 1/4 SE SE

SEC. 5 TWP. 16 RGE. 13 W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Mosar

Operator Rapid Drilling Co Address Russell - Kansas

Field _____ County Barber

Total Depth 3398 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 3/8 - 227 ft. Circulated with cement.
5/8 casing set at 3385 ft cemented & Well Tested -
10 sacks of cement dumped on bottom of hole -
Shot off & Riddled 5/8 casing - Filled with mud to
227 ft - Set Bridge & 15 sacks of cement - Mud to
36 ft - Bridge & 10 sacks of cement at the surface -
Frank Carroll - Pipe Pulling - Contractor*

C. M. Stough
District Conservation Agent

Date 11 - 7ND 1948

11-12-48

PLUGGING
FILE SEC 5 TWP 16 RGE 13 W
BOOK PAGE 67 LINE 37

COMMISSION
KANSAS