

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 50-20

LOCATION C 1/2 - NE - 11W

SEC. 5 TWP. 16 RGE. 13w

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 5 Lease Bitter "A"

Operator Cities Serv. Oil Co. Address Box 751 Great Bend Kans.

Field County Barton

Total Depth 3313 Feet.

Plugging Contractor B & W Casing Pulling Co.

Plugging Contractor's License No. 17

Address Great Bend Kans.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 7/8" (A) 325' w/ 125' of Cem. 5 1/2" set
3313' w/ 125' of Cem. Plugged back to 3166' top Perf.
3081' Casing squeezed 2147' w/ 150' of Cem. Sanded
hole to 3075' dumped 5' of Cem. Shot off and
pulled 5 1/2" casing. Mudded hole to 275' set rock
bridge and run 20' of Cem. mud to 35' set
rock bridge and 10' of Cem. to base of cellar

RECEIVED
STATE CORPORATION COMMISSION

SEP - 2 1954

CONSERVATION DIVISION
Wichita, Kansas

9-2-54

Warren H. Garner
District Conservation Agent

Date Aug 31, 1954

PLUGGING
FILE NO. 5 T 16 R 13W
BOOK PAGE 50 LINE 20