



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 73-6

LOCATION NW-NW-SW

SEC. 5 TWP. 16 RGE. 13-W

Dry Hole Abandoned Oil Well X Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 14-B Lease J. G. Ritter

Operator Shell Oil Co. Inc. Address Box #744 - Great Bend - Kans.

Field County Barton

Total Depth 3327 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 629 ft. - Circulated with cement.
4 1/2" casing set at 3316 ft. - Filled back from bottom to
3090 ft. - Dumped 5 sacks of cement at 3090 ft. - Shot off
& pulled 4 1/2" casing - Filled with mud to 500 ft. - Set rock
builder & 20 sacks of cement at 500 ft. - Mud to 250 ft. - Set rock
builder & 20 sacks of cement at 250 ft. - Mud to 30 ft. - Plug
& 10 sacks of cement at the surface

Hoggett & Lynch
Plugging Contractors

C. M. Stough
District Conservation Agent

Date 12-17-48

PLUGGING
FILE SEC 5 T 16 R 13W
BOOK PAGE 72 LINE 6

12-20-48