


15-009-16188-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barton County, Sec. 4 Twp. 16S Rge. 13W(W)  
Location as "NE/CNW/SW" or footage from lines 1680' fr. W & 330' fr. S, SW/4  
Lease Owner Phillips Petroleum Company  
Lease Name Fouts Well No. 3  
Office Address Box 779, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed May 31, 19 46  
Application for plugging filed August 15, 19 57  
Application for plugging approved August 19, 19 57  
Plugging commenced August 27, 19 57  
Plugging completed August 30, 19 57  
Reason for abandonment of well or producing formation Uneconomical to operate -  
hole in casing.  
If a producing well is abandoned, date of last production January 14, 19 57  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R. M. Brundage  
Producing formation \*Arbuckle Depth to top 3380 Bottom NR Total Depth of Well 3387 Feet  
Show depth and thickness of all water, oil and gas formations. Well was Plugged back to 3254 PB 3254  
but hole in casing stopped workover.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Stone Corral	Dry	878	NR	8-5/8"	385'	None
Lansing-Kansas City	Dry	3145	NR	5-1/2"	3381'	2692'
Arbuckle	Oil	3380	3387			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set cast iron bridge plug at 3275'. Dumped 2 sx. Calseal to 3254'. (Work done on prior workover). Mudded hole 3254' to 300'. Set rock bridge 300' to 290'. Dumped 25 sx. cement 290' to 200'. Mudded hole 200' to 15'. Dumped 5 sx. cement 15' to base of cellar. Well plugged and abandoned 3:00 P.M. 8-30-57.

RECEIVED  
CONSERVATION COMMISSION  
SEP 7 1957  
9-7-57  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
A. J. Willis (employee of owner) ~~and owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 779, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of September, 1957

My commission expires November 18, 1957 [Signature] Notary Public.

PLUGGING  
FILE SEC 4 T. 16 R. 13W  
BOOK PAGE 21 LINE 37

15-009-16188-00-00

EXPLORATION RECORD

Phillips Petroleum Company - Fouts No. 3 - SW/4 Sec. 4-16S-13W, Barton County, Kansas

Lease Fouts

Well 3

Formation Name	Top	Base	Remarks
Shale and sand	0	80	
Shale, shells and sand	80	370	
Shale and shells	370	390	
Shale and shells	390	885	
Shale and shells	885	1180	
Shale, shells and salt	1180	1565	
Shale and shells	1565	1675	
Shale and lime	1675	1750	
Lime, sandy	1750	1855	
Lime and shale	1855	1965	
Sandy Lime	1965	2165	
Broken Lime	2165	2235	
Shale	2235	2570	
Shale and lime	2570	2740	
Lime and shale	2740	2820	
Lime	2820	3065	
Lime and shale	3065	3130	
Lime	3130	3370	<u>Formation Tops</u>
Cored Lime	3370	3373	Stone Corral 878
Cored Lime and shale	3373	3375	Lansing-Kansas City 3145
Lime	3375	3381	Arbuckle 3380
Cored Lime	3381	3387	

**PLUGGING**  
 Form 883 3-53 FILE SEC 4 T. 16 R. 13W  
 BOOK PAGE 37 LINE 37

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 7 1957  
 CONSERVATION DIVISION  
 neas