


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 4 Twp. 16S Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE NE NE
Lease Owner KATHOL PETROLEUM, INC.
Lease Name Redetzke Well No. 2
Office Address 900 Sutton Place
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3/11 1969
Application for plugging filed 3/11 1969
Application for plugging approved 3/14 1969
Plugging commenced 3/11 1969
Plugging completed 3/11 1969
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3390 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/heavy mud to 600'
Set plug at 600' w/70 sx cement.
Filled hole w/heavy mud to 210'
Set plug at 210' w/20 sx cement
Filled hole w/heavy mud to 40'
Set plug at 40' w/10 sx cmt.


RECEIVED
STATE CORPORATION COMMISSION
APR 25 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KATHOL PETROLEUM, INC.
Address 900 Sutton Place Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Homer J. Catt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Homer J. Catt
Homer J. Catt
900 Sutton Place
(Address)

Subscribed and sworn to before me this 23rd day of April, 1969



Dixie Lee Brown
Dixie Lee Brown Notary Public.

KATHOL PETROLEUM, INC.

DRILLERS LOG

NO. 2 REDETZKE

SE NE NE Section 4-16S-13W

Barton County, Kansas

Commenced: 3/4/69
 Completed: 3/12/69
 Elevation: 1901 KB

FROM	TO	FORMATION	REMARKS:
215	857	Shale and redbed	Ran 6 jts., new 19#, 8-5/8" surface casing, cemented at 216' w/150 sx.
857	892	Anhydrite	
892	915	Shale and shells	
915	1425	Shale and shells	
1425	1845	Lime and shale	
1845	2080	Shale and lime	<u>ELECTRIC LOG TOPS:</u> Howard 2716' (- 815) Topeka 2791' (- 890) Heebner 3026' (-1125) Toronto 3041' (-1140) Douglas 3059' (-1158) Lansing 3106' (-1205) Base/K.C. 3301' (-1300) Arbuckle 3360' (-1459) R.T.D. 3391' (-1490)
2080	2340	Lime and shale	
2340	2775	Shale and lime	
2775	2910	Lime and shale	
2910	3005	Lime	
3005	3092	Lime	
3092	3145	Shale and lime	
3145	3150	Lime	
3150	3195	Lime	
3195	3390	Lime	
3390		Rotary total depth	

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.

Don D. Shawver
 Don D. Shawver

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me this 18th day of March, 1969.

Dixie Lee Brown
 Dixie Lee Brown, Notary



My Commission Expires: June 17, 1972

RECEIVED
 STATE CORPORATION COMMISSION
 APR 25 1969
 CONSERVATION DIVISION
 Wichita, Kansas