


15-009-20932-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barton County, Sec. 4 Twp. 16S Rge. ~~12~~ 13 (W)
Location as "NE/CNW&SW" or footage from lines SE SE NE
Lease Owner Petroleum, Inc.
Lease Name REDETZKE "D" Well No. #1
Office Address 800 RH Garvey Bldg. Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 19 1975
Application for plugging filed August 19 1975
Application for plugging approved August 19 1975
Plugging commenced August 19 1975
Plugging completed August 19 1975
Reason for abandonment of well or producing formation No commercial quantity
of oil or gas encountered.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3364 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	285'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


1st Plug Set @ 600' with 50 Sacks
2nd Plug Set @ 240' with 25 Sacks
3rd Plug Set @ 40' with 10 Sacks
Plugged rat hole with 2 Sacks
Plug was down @ 9:45 a.m. August 19, 1975

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1975 8-25-75
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jack K. Wharton-Geologist (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack K. Wharton
801 Union Center, Wichita, Kansas (Address)



Subscribed and Sworn to before me this 22nd day of August, 1975
Nancy E. Haner Notary Public
April 8, 1978

CONTRACTOR'S WELL LOG

OPERATOR:	Petroleum, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	REDEIZKE "D" #1
LOCATION:	SE SE NE Section 4-16S-13W Barton County, Kansas
GEOLOGIST:	Kenneth Johnson
SPUD DATE:	August 14, 1975
COMPLETION DATE:	August 19, 1975

0	288	Clay & Post Rock
288	445	Shale & Sand
455	860	Red beds (Shale)
860	888	Anhydrite
888	1220	Shale & Shells
1220	1865	Shale
1865	2642	Shale & Lime
2642	2880	Lime & Shale
2880	3160	Shale & Lime
3160	3364	Lime & Shale
	3364	Rotary Total Depth

Drilled 285' of 12 1/4" surface hole. Ran 7 jts. new 8 5/8" casing, Set @ 285'. Cemented with 200 sacks 60/40 Posmix, 3% ca.cl., 2% gel, Cement circulated. Plug was down @ 12:30 p.m. August 14, 1975.

Plugged and Abandoned: 1st Plug Set @ 600' with 50 Sacks; 2nd Plug Set @ 240' with 25 sacks; 3rd Plug Set @ 40' with 10 sacks; Plugged rat hole with 2 sacks. Plug was down @ 9:45 a.m. August 19, 1975. State Plugger: Duane Rankin

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack K. Wharton, Geologist of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the REDEIZKE "D" #1, SE SE NE Section 4-16S-13W, Barton County, Kansas

ABERCROMBIE DRILLING, INC.

By: Jack K. Wharton
Jack K. Wharton-Geologist

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 22nd day of August, 1975.

Nancy E. Haner
Nancy E. Haner-Notary Public

My Commission Expires: April 8, 1978

