


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County, Sec. 4 Twp. 16 Rge. 13 ~~SW~~
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C NE/4
Lease Owner Icer Addis
Lease Name REDETZKE Well No. 1
Office Address P.O. Drawer 8038 - Wichita, Ks. 67208
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole
Date Well completed September 17 19 80
Application for plugging filed Sept. 17 19 80
Application for plugging approved Sept. 17 19 80
Plugging commenced Sept. 17 19 80
Plugging completed Sept. 17 19 80
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3370'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Bottom plug set at 540' w/50 sacks cement thru drill pipe
Middle Plug set @ 280' w/30 sacks cement thru drill pipe
Top Plug set at 40' w/ $\frac{1}{2}$ sack hulls and 10 sacks cement
5 sacks cement in rat hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.
Leonard Williamson (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson
P.O. Box 823 - Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of September, 19 80.

My commission expires 4-11-1982

Dorothy M. Hogue
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1980

CONSERVATION DIVISION
Wichita, Kansas

9-23-80

DRILLERS' WELL LOG

DATE COMMENCED: September 11, 1980
 DATE COMPLETED: September 17, 1980

Icer Addis
 REDETZKE #1
 C NE/4 of Sec 4-T17S-R13
 Barton County, Kansas

ELEVATION: 1894 K.B.

0	-	53	Post Rock, Shale
53	-	196	Shale - Sane
196	-	489	Shale, Sand, Shells, Salt
489	-	853	Red Bed - Shale
853	-	879	Anhydrite
879	-	2745	Shale - Lime
2745	-	2767	Lime
2767	-	2784	Shale
2784	-	3016	Lime
3016	-	3019	Shale
3019	-	3036	Lime & Shale
3036	-	3049	Lime
3049	-	3095	Shale
3095	-	3105	Lime & Shale
3105	-	3341	Lime
3341	-	3354	Lime & Shale
3354	-	3370	Dolomite
		3370	RTD

FORMATION DATA

ANHYDRITE	853
HOWARD	2745
SEVERY	2767
TOPEKA	2784
HEEBNER	3016
TORONTO	3036
DOUGLAS	3049
BR. LIME	3095
KANSAS CITY	3105
BABE K.C.	3341
CONGLOMERATE	None
ARBUCKLE	3354
RTD	3370

SURFACE PIPE: Set used
 8-5/8" pipe @ 311'
 with 200 sacks 50/50 poz.
 2% Gel, 3%cc.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Leonard Williamson, of lawful age does swear and state that
 the facts and statements herein contained are true and correct to the
 best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 19th day of September 1980.

My Comm. Expires: 4-11-1982

Dorothy M. Hague
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 28 1980
 CONSERVATION DIVISION
 Wichita, Kansas