


WELL PLUGGING RECORD

Give All Information completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

BARTON County. Sec. 4 Twp. 16S Rge. (E) 13 (W)

Location as "NE/CNW'SW" or footage from lines C N/2 SE SW
Lease Owner PETROLEUM, INC.,
Lease Name MONROE "B" Well No. 1
Office Address ROUTE #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JANUARY 19 19 65
Application for plugging filed JANUARY 19 19 65
Application for plugging approved JANUARY 19 19 65
Plugging commenced JANUARY 19 19 65
Plugging completed JANUARY 19 19 65
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DONALD TRUAN, 634 SUNSET, RUSSELL, KANSAS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3388 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
				8-5/8"	357'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUDDED UP WITH HEAVY MUD THRU DRILL PIPE TO 350', FOLLOWED BY A WOODEN PLUG, 1/4 SACK HULLS AND 25 SACKS CEMENT. MUDDED UP WITH HEAVY MUD TO 40', FOLLOWED BY A WOODEN PLUG, 1/2 SACK HULLS AND 10 SACKS CEMENT TO BASE OF WELL CELLAR.

STATE CORPORATION COMMISSION
FEB 4 1965
24 65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) _____
ROUTE #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 2 day of FEBRUARY, 19 65

My commission expires OCTOBER 19, 1968 Notary Public.

WELL LOG

15-009-30266-00 00

COMPANY Petroleum, Inc

SEC. 4 T. 16S R. 13W

FARM Monroe

NO. B-1

LOC. N/2-SE-SW

TOTAL DEPTH 3388'


COUNTY Barton

COMM. 1-11-65

COMP. 1-19-65

CONTRACTOR Garvey Drilling Company

CASING 8 5/8" @ 357' w/250 sx



ELEVATION 1918' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 25' Surface Clay and Post Rock
- 70' Post Rock
- 110' Sand
- 240' Shale and Sand
- 357' Shells and Shale
- 585' Shale Streaks, Hard Sand and Iron
- 875' Red Bed, Shale, and Shells
- 910' Anhydrite
- 1045' Red Bed and Shale
- 1400' Shale and Lime
- 1670' Lime and Shale
- 2045' Shale and Lime
- 2150' Lime and Shale
- 2225' Shale w/Lime Streaks
- 2450' Lime and Shale
- 2875' Shale and Lime
- 2920' Lime
- 3090' Lime and Shale
- 3143' Shale and Lime
- 3180' Lime
- 3245' Lime and Shale
- 3388' Lime
- 3388' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 4 1965
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas }
 County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company
 upon oath state the above and foregoing is a true and correct copy of the log of the Monroe B-1 well.

Sam N. Stephens

Subscribed and sworn to before me this 26th day of January 1965

My Commission Expires: October 19th, 1968

David L. Freeman
 NOTARY PUBLIC