


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 16 Twp. 21 Rge. 11 (E) W(W)  
Location as "NE/CNWxSWx" or footage from lines NE SW SE  
Lease Owner Leo G. Wetherill, Jr.  
Lease Name Smith Estate Well No. 8  
Office Address 2208 Power & Light Bldg, Kansas City 5, Mo.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 4 1962  
Application for plugging filed July 4 1962  
Application for plugging approved July 4 1962  
Plugging commenced July 4 1962  
Plugging completed July 4 1962  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Herman Justus  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3500 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy hole with mud.  
Set wooden plug-1/3 sack hulls-20 sks cement-thru drill pipe at 240'  
Filled hole to 35' with heavy mud.  
Wooden plug-1/3 sack hulls-10 sks cement  
2 sks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.  
Address Box 823, Great Bend, Ks.

STATE OF KANSAS, COUNTY OF BARTON, ss.  
L.O. Chubb (employee of owner) or ~~(owner)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 823, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of July 1962.  
My commission expires June 24, 1963  
Clair E. Stimson Notary Public.

JUL 10 1962  
CONSERVATION DIVISION  
Wichita, Kansas  
10A  
7-10-62

15.185.11910.0000

W E L L L O G

Date Commenced: June 27, 1962  
Date Completed: July 4th, 1962

Leo G. Wetherill, Jr.  
SMITH ESTATE # 8  
NE SW SE Sec-16-21-11w  
Stafford County, Kansas

0	-	80	Clay & Sand
80	-	145	Shale & Red Bed
145	-	159	Sand
159	-	479	Red Bed
479	-	494	Anhydrite
494	-	780	Shale & Red Bed
780	-	1050	Shale & Shells
1050	-	1345	Salt & Shale
1345	-	1780	Shale & Lime
1780	-	2092	Lime Shale
2092	-	2660	Shale Shells
2660	-	2947	Lime Shale
2947	-	2964	Shale Lime HEEBNER
2964	-	2977	Lime TORONTO
2977	-	3076	Shale DOUGLAS
3076	-	3106	Lime Shale BROWN LIME
3106	-	3340	Lime LANSING
3340	-	3397	Chert
3397	-	3423	Sand & Shale SIMPSON
3423	-	3500	Sand & Shale RTD

Elevation: 1746 K.B.

FORMATION DATA

Anhydrite	479
Heebner	2947
Brown Lime	3076
Lansing	3106
Conglomerate	3340
Simpson	3397
R.T.D.	3500

SURFACE PIPE: Set 280'  
of 8-5/8" casing @ 278'  
with 200 sacks cement.

AFFIDAVIT

STATE OF KANSAS  
COUNTY OF BARTON) ss.

L. O. Chubb, of lawful age, does swear that the facts and statements herein contained are true and correct to the best of his knowledge.

  
L. O. Chubb - Geologist

Subscribed and sworn to before me this 6th day of July, 1962.

  
Clair E. Stinson-NOTARY PUBLIC

My Comm. Expires: June 24, 1963.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 10 1962  
CONSERVATION DIVISION  
Wichita, Kansas