

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County, Sec. 16 Twp. 21s Rge. 11 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines 150' W of SW NW NE

Lease Owner Leo G. Wetherill, Jr.

Lease Name SMITH ESTATE Well No. 12

Office Address 2208 Power & Light Bldg, Kansas City 5, Missouri

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-9 19 62

Application for plugging filed 12-9 19 62

Application for plugging approved 12-9 19 62


Plugging commenced 12-9 19 62

Plugging completed 12-9 19 62

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Justus

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3500 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 240' Set wooden plug -  $\frac{1}{4}$  sk. hulls and 20 sks. cement through drill pipe;  
Filled hole to 40' with heavy mud-set wooden plug -  $\frac{1}{4}$  sk. hulls and 10 sks. cement;  
Plugged rat hole w/2 sks. cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 11 1962  
12-11-62  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drlg. Co.

Address Box 823, Great Bend, Ks.

STATE OF KANSAS, COUNTY OF BARTON, ss.

L.O. Chubb (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Box 823, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 62.

My commission expires 6-24-63.

[Signature]  
Clair E. Stimson  
Notary Public.



15.185.12419.0000

W E L L L O G

Date Commenced: December 2, 1962  
Date Completed: December 9, 1962

Leo G. Wetherill, Jr.  
SMITH ESTATE # 12  
150' W of SW NW NE  
Section 16-21s-11 West  
Stafford County, Kansas

0	-	140'	Sand & Shale
140	-	505'	Shale & Red Bed
505	-	5529'	ANHYDRITE
529	-	660'	Red Bed
660	-	1450'	Shale Shells Salt
1450	-	1780'	Shale & Lime
1780	-	2000'	Lime Shale
2000	-	2682'	Shale & Lime
2682	-	2973'	Lime
2973	-	2978'	Shale HSEBNER
2978	-	2993'	Lime Shale
2993	-	3005'	Lime TORONTO
3005	-	3104'	Shale DOUGLAS
3104	-	3124'	Lime & Shale BROWN LIME
3124	-	3365'	Lime LANSING
3365	-	3384'	Limy CONGLOMERATE
3384	-	3425'	Shaly CONGLOMERATE
3425	-	3500'	Cherty CONGLOMERATE
3500	-		RTD

ELEVATION: 1764 K.B.

FORMATION DATA:


Hebner	2973
Brown Lime	3104
Lansing	3124
Conglomerate	3365
RTD	3500

SURFACE PIPE: Set 284' of  
8-5/8" casing at 280' with  
200 sacks cement.

AFFIDAVIT

STATE OF KANSAS  
COUNTY OF BARTON ) ss.

L. O. Chubb of lawful age does swear that he is Geologist  
for the above-named owner of the Smith Estate and that the facts and  
statements herein contained are true and correct to the best of his  
knowledge.

  
L. O. Chubb

Subscribed and sworn to before me this 10th day of December, 1962.

  
Clair E. Stinson-NOTARY PUBLIC

My Comm. Expires: 6-24-63.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 11 1962

CONSERVATION DIVISION  
Wichita, Kansas