

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 16 Twp. 21 Rge. 11 (X) W (W)

Location as "NE/CNW/SW" or footage from lines NE SE NW

Lease Owner Leo G. Wetherill, Jr.

Lease Name Smith Estate Well No. 4

Office Address 2208 Power and Light Bldg., Kansas City 5, Mo.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed December 20 19 61

Application for plugging filed December 20 19 61

Application for plugging approved 19

Plugging commenced December 20 19 61

Plugging completed December 20 19 61

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Lackamp

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3473 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 243'
Set wooden plug 1/4 sack Hulls and 20 sacks cement through drill pipe.
Filled hole to 35' with heavy mud.
Set wooden plug 1/4 sack Hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 9 1962

CONSERVATION DIVISION
Wichita, Kansas

1-8-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Company

Address Box 823, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

L. O. Chubb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. O. Chubb*

P.O. Box 823, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5 day of January, 1962

My commission expires June 24, 1963

Clair E. Stimson
Clair E. Stimson Notary Public.



RECEIVED
STATE BOARD OF RAILROAD COMMISSION

JAN 8 1962

CONSERVATION DIVISION
Wichita, Kansas

W E L L L O G

Date Commenced: December 11, 1961
Date Completed: December 19, 1961

Leo G. Wetherill, Jr.
Smith Estate # 4
NE SE NW Section 16-21-11w
Stafford County, Kansas

- 0 - 170 Sand Clay
- 170 - 494 Red Bed
- 494 - 531 ANHYDRITE
- 531 - 980 Red Bed Shale
- 980 - 1125 Shale and Shells
- 1125 - 1250 Salt
- 1250 - 1460 Shale Shells
- 1460 - 1960 Shale & Lime
- 1960 - 2635 Lime and Shale
- 2635 - 2971 Lime
- 2971 - 2976 Shale HEEBNER
- 2976 - 2988 Lime Shale
- 2988 - 3003 Lime TORONTO
- 3003 - 3102 Shale DOUGLAS
- 3102 - 3121 Lime Shale BROWN LIME
- 3121 - 3363 Lime LANSING
- 3363 - 3395 Chert CONGLOMERATE
- 3395 - 3451 Sand Shale -SIMPSON
- 3451 - 3473 Dolomite ARBUCKLE
- 3473 - R.T.D.

ELEVATION: 1760' K.B.

FORMATION DATA

Anhydrite	494
Heebner	2971
Toronto	2988
Douglas	3003
Brown Lime	3102
Lansing	3121
Conglomerate	3363
Simpson	3395
Arbuckle	3451
R.T.D.	3473

Surface Casing: Set 285' of
10-3/4" casing @ 279' with
200 sacks cement.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss.

Lewis O. Chubb, of lawful age, does swear that the facts
and statements herein contained are true and correct.



Subscribed and sworn to before me this 28th day of December, 1961.


Clair E. Stinson-NOTARY PUBLIC

My COM. Expires: 6-24-63.