

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec. 16 Twp. 21 Rge. 11 (E) West (W)

Location as "NE/CNW%SW%" or footage from lines NW NE NE

Lease Owner Leo G. Wetherill, Jr.

Lease Name SMITH ESTATE Well No. 20

Office Address 2208 Power & Light Bldg., K.C. 5, Missouri

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 3, 1964 19 64

Application for plugging filed " " 19 64

Application for plugging approved " " 19 64

Plugging commenced May 3, 1964 19 64

Plugging completed " " " 19 64

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Archie Elving

Producing formation Depth to top Bottom Total Depth of Well 3490 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 260'; set plug 1/4 sack hulls and 25 sacks cement through drill pipe
Filled hole to 40'; set plug 1/4 sack hulls, 10 sacks cement.
Plugged rat hole.

RECEIVED
STATE CORPORATION COMMISSION

MAY 5 1964

5-5-64

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF KANSAS, COUNTY OF BARTON, ss.

L. O. Chubb (employee of owner) or (owner/contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 823, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of May, 1964

My commission expires June 24, 1967

Clair E. Stimson Notary Public.



W E L L L O G

Date Commenced: April 25, 1964
 Date Completed: May 3, 1964

Leo G. Wetherill, Jr.
 SMITH ESTATE #20
 NW NE NE Sec. 16-21-11w
 Stafford County, Kansas

0 - 185' Sand & Clay
 185 - 497' Red Bed
 497 - 515' ANHYDRITE
 515 - 1255' Shale & Shells
 1255 - 1650' Shells & Shale
 1650 - 2020' Lime Shale
 2020 - 2740' Shale
 2740 - 2963' Lime
 2963 - 2967' Shale
 2967 - 2995' Lime - Shale
 2995 - 3092' Shale
 3092 - 3114' Lime Shale
 3114 - 3362' Lime
 3362 - 3439' Chert Shale
 3439 - 3490' Dolomite

ELEVATION: 1759 K.B.

FORMATION DATA:

ANHYDRITE	497
HEEBNER	2963
BROWN LIME	3092
LANSING	3114
CONGLOMERATE	3362
ARBUCKLE	3439
R.F.D.	3490

SURFACE CASING: Set 8-5/8"
 casing at 276' with 325 sacks
 cement.

A F F I D A V I T

STATE OF KANSAS)
 COUNTY OF BARTON) ss.

L. O. Chubb, of lawful age, does swear that the facts and statements herein contained are true and correct to the best of his knowledge.



 L. O. Chubb

Subscribed and sworn to before me this 5th day of May, 1964.

My Commission Expires:
June 24, 1967



 Clair E. Stimson NOTARY PUBLIC

RECEIVED
 STATE CORPORATION COMMISSION

MAY 5 1964

CONSERVATION DIVISION
 Wichita, Kansas