


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 20 Twp. 21S Rge. (E) 11(W)  
Location as "NE/CNWxSWx" or footage from lines. C NE NW SE  
Lease Owner. Abercrombie Drilling, Inc.  
Lease Name. RICHARDSON Well No. 1  
Office Address. 801 Union Center, Wichita, Kans. 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed. August 31 1965  
Application for plugging filed verbally August 30 1965  
Application for plugging approved verbally August 30 1965  
Plugging commenced August 31 1965  
Plugging completed August 31 1965  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - verbally

Name of Conservation Agent who supervised plugging of this well Archie Elbing  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3539' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	246'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole w/heavy mud to 225'  
Set 1st plug at 225' w/ 25 sx cement plus 1/4 sk hulls  
Filled hole w/heavy mud to 40'  
Set 2nd plug at 40' w/10 sx cement plus 1/2 sk hulls.  
Put 2 sk cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 8 1965  
9-8-65  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Vaughan Drilling, Inc.  
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Mildred Saxton, (employer/owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mildred Saxton  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of September, 1965

My commission expires June 16, 1967  
Leah Joyce Heike Notary Public.

## WELL LOG

COMPANY Abercrombie Drilling, Inc.  
 CONTRACTOR Vaughan Drilling, Inc.  
 FARM #1 Richardson  
 LOCATION C NE NW SE of sec. 20-21-11W  
 Stafford County, Kansas  
 ELEVATION 1748 K. B.  
 SURFACE PIPE 8 5/8" set @ 246' with 210 sx posmix sunset.  
 PRODUCTION D & A  
 COMMENCED 8-23-65  
 COMPLETED 8-31-65

<u>FORMATION</u>	<u>DEPTH</u>
Sandstone	75
Blue Shale	90
Sandstone	105
Red Bed	484
Anhydrite	491
Shale & Shells	1380
Limestone & Shale	2680
Limestone	2950
Limestone & Shale	3140
Limestone	3351
Limestone & Chert	3424
Limestone, Chert & Congl.	3480
Limestone & Conglomerate	3533
Conglomerate	3539
Rotary Total Depth	3539

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 7 1965

CONSERVATION DIVISION  
 Wichita, Kansas


FORMATION TOPS

Anhydrite	484 (+1264)
Heebner	2990 (-1242)
Toronto	3008 (-1260)
Brown Limestone	3124 (-1376)
Lansing	3149 (-1401)
Base Kansas City	3393 (-1645)
Conglomerate	3401 (-1653)
Rotary Total Depth	3539 (-1791)


A F F I D A V I T

STATE OF KANSAS., COUNTY OF BARTON, SS:

I, Donald D. Vaughan, of the VAUGHAN DRILLING, INC., being first duly sworn on oath, state; that I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

  
 Donald D. Vaughan, Pres.

Subscribed and sworn to before me this 1st day of September, 1965.

  
 Dorothy Tully, Notary Public

My commission expires: Jan. 24, 1968