

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027

Wichita, Kansas 67217
NORTH

Stafford County, Sec. 20 Twp. 21S Rge. (E) 11 (W)

Location as "NE/CNW&SW" or footage from lines NW NW NE

Lease Owner Champlin Petroleum Company

Lease Name Smith ABC Unit (Smith "C") Well No. 2

Office Address 2915 N. Lincoln, Oklahoma City, Okla. 73105

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 4-1 19 45

Application for plugging filed 10-3 19 72

Application for plugging approved 10-6 19 72

Plugging commenced 11-3 19 72

Plugging completed 11-15 19 72

Reason for abandonment of well or producing formation depleted - uneconomical to operate

If a producing well is abandoned, date of last production 7-1 19 72

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Biberstein

Producing formation Simpson Depth to top 3376 Bottom 3380 Total Depth of Well 3380 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Simpson	Oil	3376	3380	8 5/8"	248	None
				4 1/2"	3376	1524

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

checked bottom, filled hole with sand to 3350' and dumped 3 sacks of cement. Filled hole with sand to 3000' and dumped 3 sacks cement. Loaded hole and shot 4 1/2" casing at 2600', 2414', 2222', 2020', 1940', 1842', 1764', 1654', and 1554'. Pulled 48 joints of 4 1/2" casing or 1524'. Bailed hole to 280', set 20' rock bridge and dumped 4 yards ready-mix cement. Plugging complete on 11-15-72.

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co., Inc.

Address Chase, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.
Harold E. Melvin (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold E Melvin
2915 N. Lincoln, Oklahoma City, Okla. 73105
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December 19 72
Notary Public.

My commission expires OCT 8 1975

(For use in Kansas only for reporting formation records)

WELL RECORD

COUNTY Stafford SEC. 20 TWP. 21S RGE. 11W
 COMPANY OPERATING Champlin Refining Company
 OFFICE ADDRESS Enid, Oklahoma
 FARM NAME Smith "C" WELL NO. 2
 WELL LOCATED 420' south of North Line &
2100' feet West of East Line of NE 1/4
 CHARACTER OF WELL Oil

Drilling started: _____ Completed: _____

CASING RECORD

SIZE	WT.	THDS.	MAKE	FT.	IN.	Amount PULLED	CEMENT
8 5/8" OD	32#	8rd		248'			125 sax
4 1/2" OD	9.50#	8rd		3376'			100 sax

FORMATION RECORD

FORMATION	TOP	BOTTOM	FORMATION	TOP	BOTTOM
Sand	0	100	Lime	3175	3375
Redbed	100	495	Cored	3375	3380
Lime	495	520	T. D.	3380	
Shale	520	630			
Shle & Lime Shells	630	1015			
Shale & Salt	1015	1220			
Shale & Shells	1220	1375			
Lime & Sh	1375	1490			
Lime	1490	1665	Top, Anhydrite		495
Lime & Shale	1665	1850	" Topeka		2717
Lime	1850	2065	" Lansing		3122
Lime & Shale	2065	2140	" Simpson Sand		
Shale	2140	2205	Detrital Zone		3373
Shale & Lime	2205	2250			
Shale	2250	2440			
Lime	2440	2540			
Shale & Lime	2540	2730			
Lime	2730	2760			
Shale & Lime	2760	2840			
Kune	2840	2980			
Lime & Shale	2980	3035			
Lime	3035	3090			
Shale	3090	3145			
Lime & Shale	3145	3175			

RECEIVED
STATE CORPORATION COMMISSION

OCT 6 1972

CONSERVATION DIVISION
Wichita, Kansas

J. H. Wentworth
Superintendent.

Subscribed and sworn to before me this
25th day of June 1945

G. E. Miller
Notary Public

My Commission Expires:

Dec. 7, 1945