

15.185.21567.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED-4
STATE CORPORATION COMMISSION
REV. 12-15-80
SEP 7 1982
CONSERVATION DIVISION
Wichita, Kansas
9-7-82

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 29 TWP. 21 RGE. 14 E/W
Location as in quarters or footage from lines:
NE/SW/SE

Lease Owner Woodman-Iannitti Drilling Company
Lease Name Kirkman Well No. #1
Office Address 104 S. Broadway - Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed _____
Application for plugging filed _____
Plugging commenced August 20, 1982
Plugging completed August 27, 1982
Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation _____ Depth to top _____ bottom _____ T.D. 3810'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	286'	NONE
				5 1/2"	3809'	2871.17'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Dumped sand to 3575' and five (5) sacks cement.
Shot pipe @ 3090' and 2950'.
Pulled eighty-seven (87) joints 5 1/2" casing.
Squeezed well with four (4) sacks hulls, twenty-five (25)
sacks cement, twenty-five (25) sacks gel, one (1) sack
hulls, one hundred twenty-five (125) sacks 50/50 pozmix
cement with 4% added gel and 3% calcium chloride.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
JAMES W. ROCKHOLD - Box 698 - Great Bend,
(Address) Ks. 67530

SUBSCRIBED AND SWORN TO before me this 3rd day of Sept, 1982



Margaret Prosser
Notary Public.

My Commission expires:

15.185.21567.0000

K. T. WOODMAN
REG. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

1008 DOUGLAS BUILDING
104 S. BROADWAY
WICHITA, KANSAS 67202

July 15, 1982

Company:	Woodman & Iannitti Drilling Co.
Farm:	#1 Kirkman
Location:	NE SW SE
Section:	29-21-14W
County:	Stafford
Contractor:	Woodman & Iannitti Drilling Co.
Comm:	March 23, 1982
Comp:	April 20, 1982
Total Depth:	3810'
Casing:	Set 8-5/8" @ 285' w/225 sx.

Figures Indicate Bottom Formations:

230	Sand
285	Shale w/ Sand Streaks
666	Shale & Red Bed
872	Shale
905	Anhydrite
1205	Shale
1755	Shale
2040	Shale
2293	Shale & Lime
2493	Shale & Lime
2743	Lime & Shale
2955	Lime & Shale
3135	Lime & Shale
3258	Lime & Shale
3390	Lime & Shale
3485	Lime & Shale
3570	Lime & Shale
3638	Lime & Shale
3657	Lime & Shale
3691	Lime
3787	Lime
3810	Lime & Arbuckle

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1982
CONSERVATION DIVISION
Wichita, Kansas

I certify the above to be a true and correct copy of the drillerslog to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

K.T. Woodman
K.T. Woodman, Partner