


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

STAFFORD County, Sec. 29 Twp. 21s Rge. 14 (X) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner PETROLEUM, INC.,

Lease Name LINCOLN Well No. 2

Office Address R. R. #2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL

Date well completed NOVEMBER 3 19 51

Application for plugging filed MARCH 11 1969

Application for plugging approved MARCH 12 1969

Plugging commenced MARCH 19 19 69

Plugging completed MARCH 22 19 69

Reason for abandonment of well or producing formation DEPLETION OF PRODUCING ZONE

If a producing well is abandoned, date of last production MAY 19 19 68

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well R. J. WAREEN

Producing formation ARBUCKLE Depth to top 3795 Bottom 3800 Total Depth of Well 3800 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
ARBUCKLE	SLIGHT AMOUNT OF OIL & WATER	3798	3800	8-5/8"	253	NONE
				5-1/2"	3798	2924'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGED BACK WITH SAND FROM 3800 TO 3500. MIXED AND DUMPED 5 SACKS OF CEMENT FROM 3500' TO 3460'. MIXED AND PUMPED IN 15 SACKS OF GEL MUD. MIXED AND PUMPED IN 75 SACKS OF CEMENT FROM 2250' TO BASE OF WELL CELLAR.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 3 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor RUSS CASING PULLING, INC.,

Address Box 1082, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.

MONTE CHADD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) *Monte Chadd*

R. R. #2, GREAT BEND, KANSAS 67530 (Address)

SUBSCRIBED AND SWORN TO before me this 31 day of MARCH, 19 69

*Richard H. Dumbler*  
Notary Public.

My commission expires MAY 28, 1969

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
502 East Murdock,  
Wichita, Kansas


COPY  
15.185.10814.0000

Company: PETROLEUM INC.  
Farm: Lincoln No. 2

SEC. 29 T. 21 R. 14W  
SE SE SE

Total Depth. 3800  
Comm. 10-14-51 Comp. 10-25-51  
Shot or Treated.  
Contractor. Garvey Oil  
Issued. 2-23-52

County. Stafford  
KANSAS



Elevation. 1917 R.B.

Production. I.P.P. 81 BO & 10% W.

CASING:

8 5/8" 253' cem. w/175 sx  
5 1/2" 3799' cem. w/125 sx

Figures indicate Bottom of Formations.

surface soil & sand	40
sand	225
shale & shells	320
sand	410
red bed & shale	670
red bed	864
anhydrite	892
shale & shells	920
salt	1295
shale & shells	1550
shale & lime	3125
lime	3318
lime & shale	3425
lime	3659
lime & shale	3699
chert	3740
shale & lime	3778
shale	3800 RTD
Total Depth	

Tops:	
Heebner	3294
Brown Lime	3411
Lansing	3421
Base-Kansas City	3649
Arbuckle	3796

RECEIVED  
STATE CORPORATION COMMISSION  
APR 3 1969  
CONSERVATION DIVISION  
Wichita, Kansas