


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

— Stafford — County. Sec. 29 Twp. 21S Rge. 14W (E) — (W)
Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner Alpine Drilling Co., Inc.
Lease Name Weirauch Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed November 18, 1969 19
Application for plugging filed June 18, 1970 19
Application for plugging approved June 19, 1970 19
Plugging commenced July 6, 1970 19
Plugging completed July 14, 1970 19
Reason for abandonment of well or producing formation Not productive in commercial quantities
If a producing well is abandoned, date of last production March 22 1970
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein
Producing formation Arbuckle Depth to top 3786 Bottom _____ Total Depth of Well 3790 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	249 ft.	Cemented
				5 1/2"	3785 ft.	1698 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 3770 feet to 3700 feet. Ran 5
sacks of cement from 3700 feet to 3670 feet. Pumped
30 sacks of gel mud and 100 sacks of cement to plug well.

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jon T. Williams, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Jon T. Williams, Jr.
800 Bitting Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of August, 19 70

December 10, 1972

Evelyn Wanko
Evelyn Wanko
Notary Public.



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1970
CONSERVATION DIVISION
Wichita, Kansas.

WEIRAUCH #1
C SW NW Section 29-21S-14W
Stafford County, Kansas

Commenced: September 17, 1969
Completed: September 25, 1969

OPERATOR - Alpine Drilling Co., Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	248	Surface clay, sand, shale, shells	
248	330	Shale and red bed	Ran 12 joints of 8-5/8" casing, set @ 248' w/250 sacks cement.
330	440	Sand	
440	875	Red bed	
875	900	Anhydrite	
900	1496	Shale and shells	
1496	3360	Lime and shale	
3360	3788	Lime	
3788	TD		Ran 17 joints of 5-1/2" casing, set 3' off bottom @ 3785' w/125 sacks cement.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C SW NW Section 29-21S-14W, Stafford County, Kansas, to the best of my knowledge and belief.

E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 1 day of October, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton, Notary Public

