

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 29 Twp. 21S Rge. 14 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines NW SE NW
Lease Owner Thor Corporation
Lease Name Weirauch Well No. 2
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 4-30-1953 19 53
Application for plugging filed 5-21 19 62
Application for plugging approved 5-23 19 62
Plugging commenced 5-23 19 62
Plugging completed 5-31 19 62
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 4-30 19 62
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W.L. Leckamp
Producing formation arbuckle Depth to top _____ Bottom _____ Total Depth of Well 3791 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	228'	none
				5 1/2	3790'	2780'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 3791' to 3760'. Mixed and dumped 5 sx. cement from 3760' to 3720'. Pulled 2780' of 5 1/2" csg. Mixed and pumped in 10 sx. gel mud. Put in plug. Mixed and pumped in 80 sx. cement. Filled to base of cellar. Shut in with 50# psi.

RECEIVED
STATE CORPORATION COMMISSION

JUN 4 1962 U-4-62

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Acé Pipe Pulling Company (Lisence #2)
Address Box 304, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
Wm. D. Hoberrecht (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.D. Hoberrecht
Great Bend Kans (Address)

SUBSCRIBED AND SWORN to before me this 1st day of June, 1962
Shuley J. Mares Notary Public.

My commission expires March 1, 1966

INVOICED

DATE 6/5/62
INV. NO. 5098-W

DRILLERS LOG (COPY)

Company:
Contractor:
Farm

Westgate-Greenland Oil Co.
Westgate Drilling Corp.
Weirauch # 2 NW SE NW Sec. 29-21s-14 W
Stafford, County, Kansas.

Commenced: April 10 1953
Completed: April 30 1953
Elevation: 1947 DF

0 to 211	Sgil. sand and clay		
211 to 320	Shale and shells	Tops:	
320 to 420	Sand	Anhydrite	880
420 to 615	Red bed and shells		
615 to 880	Red bed and shale	Heebner	3289
880 to 905	Anhydrite		
905 to 1240	Shale and shells	Brown ls	3402
1240 to 1430	Shale, shells w/salt		
1430 to 1575	Shale and shells	Lansing	3414
1575 to 1725	Lime and shale		
1725 to 1915	Lime	Base K C	3638
1915 to 2055	Shale and lime		
2055 to 2785	Shale and lime	Certy Cong	3664
2785 to 2830	Lime		
2830 to 2935	Lime and shale	Viola	3677
2935 to 3050	Lime		
3050 to 3223	Lime and shale	Simpson	3723
3223 to 3294	Lime		
3294 to 3297	Shale	Arbuckle	3777
3297 to 3306	Lime		
3306 to 3363	Lime and shale		
3363 to 3406	Shale W/sand streaks		
3406 to 3430	Lime and shale		
3430 to 3642	Lime		
3642 to 3683	Shale, Lime W/ chert		
3683 to 3723	Chert-shale and lime		
3723 to 3779	Shale		
3779 to 3794	Arbuckle		
3794	T. D. (RB)		

Certified by Harold A. Burt and witnessed by Esther Unsell Notary Public

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1962
CONSERVATION DIVISION
Wichita, Kansas