

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County. Sec. 29 Twp. 21 Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NE NW

Lease Owner SANTA FE PIPE & SUPPLY

Lease Name WEIRAUCH Well No. 1

Office Address P. O. BOX 562 - GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed OCTOBER 31 19 52

Application for plugging filed MAY 21 19 62

Application for plugging approved MAY 23 19 62


Plugging commenced MAY 22 19 62

Plugging completed MAY 28 19 62

Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES - VERBALLY



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. LACKAMP

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3817 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		1796'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3817' - 3760' SAND
 3760' - 3730' 5 SACKS CEMENT
 3730' - BASE 10 SACKS MUD - 80 SACKS CEMENT

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 30 1962
 CONSERVATION DIVISION
 Wichita, Kansas
 7-30-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GLENN & SMITH PIPE PULLING COMPANY

Address P. O. BOX 114 - ELLINWOOD, KANSAS

STATE OF Kansas, COUNTY OF Barton, ss.
Santa Fe Pipe & Supply (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P.O. Box 562 - Great Bend, Kans. (Address)

SUBSCRIBED AND SWORN TO before me this 26 day of July, 19 62

My commission expires Jan 26, 1963.
Carmen Reinhardt Leiker Notary Public.


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WESTGATE-GREENLAND OIL COMPANY
Farm- Weirauch No. 1

SEC. 29 T. 21 R. 14W
S. 1 NE NW

Total Depth. 3820 RB
Comm. 10-11-52 Comp. 10-31-52
Shot or Treated.
Contractor. Westgate Drlg. Corp.
Issued. 12-20-52

County Stafford
KANSAS



CASING:

8 5/8" 247' com. w/225 sx
5 1/2" 3817' com. w/100 sx

Elevation 1944 LF

Production. 25 BOPD

Figures indicate Bottom of Formations.

shale & shells	60
shale & sand	213
shale & shells	247
shale	300
sand	405
red bed & shale	705
shale & sand	874
anhydrite	905
shale & shells	1210
shale & salt	1375
shale, salt & shells	1465
shale & shells	1620
lime	1635
shale & shells	1720
lime & shale	1790
lime	2150
shale & lime	2925
lime	2940
lime & shale	3217
lime	3243
lime & shale	3414
lime	3615
lime & shale	3676
lime & chert	3680
lime	3730
lime & shale	3750
shale & sand	3782
lime	3820 RB
Total Depth	

Tops:	
Anhydrite	872
Heebner	3288
Toronto	3315
Base <u>Orcad</u>	3327
Brown Lime	3401
Lansing	3412
Base-K.C.	3636
Viola	3676
Simpson	3718
Arbuckle	3778

- L DST: #1 3545-59' 1 hr.
30' sli. oil cut mud no BHP.
- S DST: #2 3735-64' 1 hr. 35'
mud 930# BHP
- A DST: #3 3780-88' 1 hr. 950'
fluid all good oil, 900# BHP
- DST: #4 3788-98' 1 hr. 2355'
- P sli. oil cut sul. wtr 1245# BHP.

Schlumberger run.
Perf. 36 holes 3782-85' 47 holes
3777-82' swabbed 8 hr. 61.43 BO
5% wtr. 20 gravity oil.

RECEIVED
STATE CORPORATION COMMISSIONER
JUL 30 1962
CONSERVATION DIVISION
Wichita, Kansas