

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County, Sec. 29 Twp. 21S Rge. 14W (N) X(W)

Location as "NE/CNW/SW" or footage from lines SE NE SE  
Lease Owner PETROLEUM, INC.  
Lease Name LINCOLN Well No. 5  
Office Address ROUTE 2, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed APRIL 8, 1962  
Application for plugging filed APRIL 8, 1962  
Application for plugging approved APRIL 8, 1962  
Plugging commenced APRIL 8, 1962  
Plugging completed APRIL 8, 1962  
Reason for abandonment of well or producing formation NO PRODUCIBLE FORMATIONS

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W.L. LACKAMP  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3828 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	256'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 220'. FOLLOWED BY WOODEN PLUG. PLACED 20 SACKS OF CEMENT THROUGH DRILL PIPE ON TOP OF THE PLUG. MUDDED UP WITH HEAVY MUD TO 35' FOLLOWED BY A WOODEN PLUG. PLACED 10 SACKS OF CEMENT ON TOP OF PLUG TO BASE OF WELL CELLAR.

RECEIVED  
STATE CORPORATION COMMISSION  
4-30-62  
APR 30 1962

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY  
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
DON SEARLE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. DON SEARLE, DIST. PROD. SUPT.  
(Signature) *Don Searle*  
ROUTE 2, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 27TH day of APRIL, 1962

My commission expires APRIL 14, 1963. *Arthur J. ...* Notary Public.



# WELL LOG

15.185.11357.0000

COMPANY PETROLEUM, INCORPORATED

SEC. 29 T. 21S R. 14W

FARM LINCOLN NO. 5


LOC. SE, NE, SE

TOTAL DEPTH 3828'

COUNTY STAFFORD CO., KANSAS

COMM. March 31, 1962 COMP. April 8, 1962

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 256' w/225 sax.

ELEVATION 1944' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

115	Surface clay, sand & gravel
220	Sand, gravel & shale
256	Red bed
860	Red bed & shale
890	Anhydrite
1730	Shale & shells
1795	Shale & lime
2215	Lime
2610	Lime & shale
2940	Shale & lime
3410	Lime & shale
3735	Lime
3785	Lime & chert
3800	Sand
3828	Lime
3828	T. D.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 APR 30 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

State of KANSAS }  
 County of BARTON } ss

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #5 LINCOLN well.

*Verne A. Morris*

Subscribed and sworn to before me this 25th day of April 19 62

My Commission Expires: April 14, 1963

*Arthur J. Wiles*  
 NOTARY PUBLIC