

- 1 - State Corp. Comm. ✓
- 1 - B. A. Conner
- 1 - Mary Crump
- 1 - File

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Stafford SEC. 29 TWP. 21 RGE. 14W E/W
 Location as in quarters or footage from lines:
302' from W line 990' from S line

Lease Owner Phillips Petroleum Company
 Lease Name Lincoln "A" Well No. 4
 Office Address Box 287 Great Bend, Ks. 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 7/28/82
 Application for plugging filed 7/28/82
 Plugging commenced 7/28/82
 Plugging completed 7/28/82
 Reason for abandonment of well or producing formation Dry Hole

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3885
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	419'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Rigged HOWCO & plugged well as follows with 4 1/2" Drill Pipe. 1st plug, 50 sx 50-50 pozmix, 4% gel 3% CaCl @ 3750'. 2nd plug 70 sx 50-50 pozmix, 4% gel 3% CaCl @ 780'. 3rd plug 40 sx 50-50 pozmix, 4% gel 3% CaCl @ 480'. 4th plug, 10 sx 50-50 pozmix 4% gel 3% CaCl in rat hole. Completed 1:30 PM 7/28/82.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Halliburton Oil Well Cementing

STATE OF Kansas COUNTY OF Barton, ss.
C. D. Dohrer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. D. Dohrer
Box 287 - Great Bend, Ks. 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 82
Lisa M. Grayer
 My Commission expires: November 17, 1985



RECEIVED
 STATE CORPORATION COMMISSION

JUL 30 1982

CONSERVATION DIVISION
 Wichita, Kansas

EXPLORATION RECORDLease Lincoln "A"Well 4

Formation Name	Top	Base	Remarks
Sand & Surface Clays	0	210	
Sand & shale	210	405	
Redbed	410	1010	
Shale & Shells	1010	1450	
Lime & Shells	1450	1670	
Lime	1670	2010	
Lime & shale	2010	2700	
Shale	2700	2780	
Lime & shale	2780	3017	
Lime	3017	3310	
Lime & shale	3310	3425	
Lime	3425	3650	
Lime & chert	3650	3786	
Lime	3786	3815	
Lime & chert	3815		
LOG FORMATION TOPS:			
Anhydrite	865		
Heebner	3326		
Toronto	3350		
Douglas	3368		
Brown Lime	3444		
LKC	3456		
Marmaton	3706		
Viola	3750		
Simpson shale	3791		
Simpson sand	3805		
Arbuckle	3840		