

15.185.10816.0000

Offig-State Corp Comm.

Copy - Well Records-B'ville

Copy-OKC Office Copy-Well File

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185

LEASE NAME Stafford

WELL NUMBER 1

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 29 TWP. 21 RGE. 14 RRXXR(W)

COUNTY Stafford

Date Well Completed 1-20-86

Plugging Commenced 11-1-85

Plugging Completed 11-14-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Route #3, Box 20-A, Great Bend, Ka 67530

PHONE#(316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation LKC Depth to Top 3480 Bottom 3578 T.D. PR 3633'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface	Water	0'	414	9 5/8"	414	-0-
Production	Oil & wtr	0'	3827	7"	3827'	-0-


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

11-1-85 MIRU Chase WS & LD rods, tbg & pmp. 11-13-85 MIRU B-J Titan Serv & hook up to 7" cag. Pmp 50 sx Class A Com Cmt w/37 sx gel & 2 sx bulls. Rel 7" wiper plug follow by 180 w/180 sx 60-40 Pozmix w/6% gel. Pmp into 9 5/8" annulus-press to 1000#-held. Max press 1000#, SIP 300# State Rep, Buddy Metz, on loc. RDMO B-J Titan. Cut off cag & weld on plate. P&A 11-14-85 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Titan Service License No. \_\_\_\_\_

Address Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.



Kaare A. Westby, Area Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kaare Westby  
Kaare A. Westby, Area Manager  
(Address) Route #3, Box 20-A Great Bend, Ka

SUBSCRIBED AND SWORN TO before me this 4th day of December, 19 85

Velma L. Mog  
Notary Public

My Commission Expires: February 15, 1988

RECEIVED  
STATE CORPORATION COMMISSION

Form CP-4  
Revised 08-84

DEC 19 1985

12-19-85

CONSERVATION DIVISION

15.185.10916.0000

EXPLORATION RECORD

1 - lls. Prod.  
 1 - Division  
 1 - District  
 1 - Geological Dept. - Evils.  
 1 - Geological Dept. - District

Lease Lincoln "A"Well 1

Formation Name	Top	Base	Remarks
Sand	0	210	
Sand and shale	210	414	
Redbed	414	571	
Redbed and shale	571	1018	
Shale and shells	1018	1466	
Lime and shells	1466	1684	
Lime	1684	2028	
Lime and shale	2028	2732	
Shale	2732	2795	
Lime and shale	2795	3035	
Lime	3035	3316	
Lime and shale	3316	3438	
Lime	3438	3650	
Lime and chert	3650	3757	
Lime	3757	3797	
Lime and chert	3797	*3829	
<u>FORMATION TOPS (Sample)</u>			*Not penetrated at 3829' TD.
Heebner	3288		
Toronto	3308		
Douglas	3318		
Brown Limestone	3404		
Lansing-Kansas City	3415		
Base-Kansas City	3643		
Marmaton	3650		
Viola	3696		
Simpson Shale	3732		
Simpson Sandstone	3750		
Arbuckle	3785		
Rotary Total Depth	3829		
Cable Tool Total Depth PB	3775		

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 25 1935  
 CONSERVATION DIVISION  
 Wichita Kansas