


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Pawnee County. Sec. 27 Twp. 21S Rge. (E) 16 (W)

Location as "NE/CNW%SW%" or footage from lines. C W/2 W/2 W/2
Lease Owner Sunray Mid-Continent Oil Company
Lease Name Larned Unit #3 Well No. 1
Office Address Box 788, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 8-14-53 19 60
Application for plugging filed April 8 19 60
Application for plugging approved April 11 19 60
Plugging commenced April 20 19 60
Plugging completed April 27 19 60
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production February 24 19 60
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Arbuckle Depth to top 3873 Bottom 3878 Total Depth of Well 3878 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing		3513	3728	8-5/8	1000	None
Marmaton		3770		5-1/2	3865	3028'
Conglomerate		3788				
Arbuckle		3864				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand to 3850' and dumped 5 sacks cement.
Pulled 5 1/2 casing and mudded hole with 40 bbl. mud.
Set rock bridge at 290' and dumped 25 sacks cement.
Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to bottom of cellar. Mud to surface.

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1960
CONSERVATION DIVISION
Wichita, Kansas
5-10-60

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
James R. Nichols (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 788, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9 th. day of May, 19 60

My commission expires December 24, 1960 [Signature] Notary Public.



Sunray Oil Corporation
Tulsa, Oklahoma

Tulsa, Oklahoma
August 10, 1953

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: July 24, 1953
Drilling Completed: August 7, 1953

Larned Unit 3 #1 NW-
SW-Section 27-21S-16W
Pawnee County, Kansas.

DRILLERS LOG

Sand	0-80
Surface Clay	80-195
Shale	195-300
Shale & Shells	300-425
Dakota Sand	425-530
Red Bed	530-1001
Anhydrite	1001-1015
Shale & Shells	1015-1765
Shale & Lime	1765-1900
Lime	1900-1945
Lime & Shale	1945-2025
Shale & Lime	2025-2280
Lime & Shale	2280-2535
Shale & Lime	2535-2620
Lime & Shale	2620-2650
Shale & Broken Lime	2650-2770
Broken Lime & Shale	2770-2955
Lime-Shale	2955-3030
Lime	3030-3105
Broken Lime	3105-3180
Lime Shale	3180-3235
Lime	3235-3450
Shale & Lime	3450-3515
Lime & Shale	3515-3557
Lime	3557-3673
Lime & Shale	3673-3755
Marmaton	3755-3800
Shale & Lime	3800-3833
Simpson	3833-3864
Arbuckle	3864-3867

RECEIVED
STATE CORPORATION COMMISSION

MAY 10 1960

TD CONSERVATION DIVISION
Wichita, Kansas

I, Frank E. Stickle, hereby certify the above to be a true and complete drillers log of Sunray Oil Corporation's Larned Unit 3-#1 NW-SW-Section 27-21S-16W, Pawnee County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1956

My commission expires