

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely,
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Pawnee County, Sec. 27 Twp. 21 Rge. 16 (E) (W) X

Location as "NE/CNW/SW" or footage from lines CNL SW SW

Lease Owner A. L. Abercrombie Inc.

Lease Name Morris Well No. #3

Office Address 801 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 2-28-72 19


Plugging commenced 3-18-72 19

Plugging completed 3-21-72 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3861 1/2 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2'	3848'	2646.87'
				8 5/8"	986'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3825'. Mixed and ran 5 sacks cement thru dump bailer.

Mudded hole to 375' - set 25' rock bridge. Filled hole with 5 yards ready-mix from 350' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1972
CONSERVATION DIVISION
Wichita, Kansas
3-23-72

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer


Box 364 Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of March, 1972.

My commission expires 24 October 1972

Sidney D. Miller
Notary Public.



CONTRACTOR'S WELL LOG

COMPANY: Hingrove Petroleum Corporation
 CONTRACTOR: Hingrove Petroleum Corporation
 WARRIS: Morris # 3
 LOCATION: C&L 67427 Section 27-21-16
 Pawnee County, Kansas

COMMENCED: March 25, 1953
 COMPLETED: April 6, 1953

0	60	Surface soil and sand
60	90	Shale, sand and streaks
90	355	Shale
355	415	Shale, sand streaks
415	520	Sand
520	680	Shale and shells
680	785	Shale, sand and red bed
785	975	Red bed
975	986	Anhydrite
986	1800	Shale
1800	2001	Shale and shells
2001	3244	Lime and shale
3244	3247	Lime
3247	3249	Artificial
	3249	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 28 1972
 CONSERVATION DIVISION
 Wichita, Kansas

Set 3 5/8" at 981 with 450 lbs of cement.

Set 2 1/2" casing at 3248 with 150 sacks of cement.

STATE OF KANSAS }
 COUNTY OF SEDGWICK }

I, GEORGE L. STELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the Morris # 3, C&L 67427-Section 27-21-16, Pawnee County, Kansas, as reflected by the files of the Hingrove Petroleum Corporation.

HINGROVE PETROLEUM CORPORATION

Edward G. Bell
 Secretary-Treasurer

Subscribed and sworn to before me a Notary Public in and for Sedgewick County, Kansas, this 11th day of April, 1953.

Mary L. Luman
 Notary Public

My Commission Expires: November 14, 1956.