

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County. Sec. 27 Twp. 21 Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines C SW NE NE

Lease Owner McAdams Pipe & Supply Company

Lease Name W. K. Bell Well No. 6

Office Address 2700 N. Main, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed _____ 19____

Application for plugging filed _____ 19____

Application for plugging approved _____ 19____

Plugging commenced June 26 19 63

Plugging completed July 10 19 63

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3876 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	985	8 5/8"	985	none
		0	3850	5 1/2"	3850	2733.93

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand back to 3840', set 10' rock bridge and dump 5 sacks of cement.

Mud back to 400' and dump 20 sacks of cement. Fill with mud to

180' and dump 20 sacks of cement. Mud to 30' and cap with 10

sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Dean Wells (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells

Ellinwood, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 19 63

My commission expires July 7, 1964

Notary Public.

CONTRACTOR'S WELL LOG

COMPANY: Gulf Oil Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: W. K. BELL #6
 LOCATION: C. SW NE NE, Sec. 27-21S-16W
 Pawnee County, Kansas.
 COMMENCED: October 11, 1953
 COMPLETED: October 27, 1953

0	112	Sand and gravel
112	320	Blue shale & shells
320	415	Blue shale & red bed
415	540	Sand & shells
540	894	Shale & shells
894	985	Anhydrite
985	1826	Shale & shells
1826	2100	Shale & lime
2100	2350	Lime
2350	3605	Shale & lime
3605	3647	Lime
3647	3874	Lime & shale
3874	3876	Arbuckle
	3876	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

JUN 6 1963

CONSERVATION DIVISION
Wichita, Kansas

Set 8-5/8" casing at 990' with 425 sacks cement.
 - Set 5-1/2" casing at 3875' with 150 sacks cement.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the W. K. BELL #6, C SW NE NE, Section 27-21S-16W, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY *Gordon L. Koelling*
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 2nd day of November, 1953.

William L. Stinson
 Notary-Public

My commission expires September 24, 1956.