


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 27 Twp. 21 Rge. 16 (E) 16 (W)
Location as "NE/CNW%SW%" or footage from lines C NE NE NE
Lease Owner McAdams Pipe & Supply Company
Lease Name W. K. Bell Well No. 7
Office Address 2700 N. Main, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced June 22 19 63
Plugging completed July 10 19 63
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3879 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	972	10 3/4"	972	none
		0	3857	7"	3857	2618.02

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand back to 3830', set 10' rock bridge. Mixed 5 sacks of cement and dumped at 3820'. Filled with mud back to 400' and dumped 25 sacks of cement. Filled with mud to 180' and dumped 25 sacks of cement. Filled with mud to 25' and capped with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1963
7-22-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Dean Wells (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 19 63

My commission expires July 7, 1964 Notary Public.

15.145.00772.0000

W. K. HILL 7
CENTER NE NE 1/4 SECTION 27-21S-16W
PAWNEE COUNTY, KANSAS
GULF OIL CORPORATION

10-3/4" O. D. casing cemented at 980'
 7" O. D. casing cemented at 3862'

Drilling commenced November 2, 1953
 Drilling completed November 22, 1953

FROM	TO	FORMATION	REMARKS
0'	140'	Sand	
140	422	Shale	
422	520	Sand	
520	730	Red bed	
730	950	Red bed & shells	
950	977	Red bed	
977	1002	Anhydrite	10-3/4" O. D. casing cemented with 700 sacks cement at 980'
1002	1800	Shale & shells	
1800	1890	Broken lime	
1890	2080	Lime broken	
2080	2200	Lime & shale	
2200	2340	Broken lime	
2340	2460	Shale & lime	
2460	2590	Shale	
2590	3050	Shale & lime	
3050	3115	Lime & shale	
3115	3420	Lime	
3420	3480	Shale & lime	
3480	3805	Lime	
3805	3840	Lime & shale	
3840	3856	Shale	Coring 3856' - 3879'
3856	3879	Lime	7" O. D. casing cemented with 100 sacks regular cement at 3862'
T. D.	3879'		