


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County, Sec. 27 Twp. 21 Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines C NW NE NE
Lease Owner McAdams Pipe & Supply Company
Lease Name W. K. Bell Well No. 8
Office Address 2700 N. Main, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced June 28 19 63
Plugging completed July 10 19 63
Reason for abandonment of well or producing formation depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3873 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	977	8 5/8"	977	none
		0	3870	5 1/2"	3870	2703.45

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 3850. Set 10' rock bridge. Mixed 5 sacks of cement and dumped at 3840'. Filled hole with mud back to 400' and dumped 20 sacks of cement. Fill with mud to 180' and dump 20 sacks of cement. Fill with mud to 30' and cap with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
7-22-63
JUL 22 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Dean Wells (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 1963

My commission expires July 7, 1964 [Signature] Notary Public.

15.145.00773.0000

W. K. BELL 8
NW NE NE SEC. 27-21E-16W
PAWNEE COUNTY, KANSAS
GULF OIL CORPORATION

8-5/8" O. D. Casing Cemented at 985'
 5-1/2" O. D. Casing Cemented at 3878'

Drilling commenced March 7, 1954
 Drilling completed March 18, 1954

FROM	TO	FORMATION	REMARKS
0'	135'	Sand	
135	295	Shale & shells	
295	424	Shale	
424	515	Sand	
515	980	Red bed	
980	996	Anhydrite	8-5/8" O. D. casing cemented with 430 sacks cement at 985'
996	1120	Red bed & shale	
1120	1715	Shale & shells	
1715	1970	Shale & lime	
1970	2230	Lime	
2230	2380	Lime & shale	
2380	2500	Lime	
2500	2610	Shale & shells	
2610	2755	Shale	
2755	3135	Shale & lime	
3135	3385	Lime	
3385	3465	Lime & shale	
3465	3525	Shale & lime	
3525	3760	Lime	
3760	3805	Lime & chert	
3805	3855	Sand & shale	
3855	3873	Shale & sand	
3873	3878	Lime	5-1/2" O. D. casing cemented with 100 sacks bulk cement at 3878'
T.D.	3878'		

STATE OF KANSAS
 STATE GEOLOGICAL SURVEY

July 27 1954

GEORGE WATSON, DIRECTOR
 Wichita, Kansas