

15.145.01467.0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027

WELL PLUGGING RECORD

Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 27 Twp. 21 Rge. (E) 16(W)
Location as "NE/CNWESW" or footage from lines NE SW NE
Lease Owner Pipe Pullers, Inc.
Lease Name W. K. Bell Well No. 3
Office Address Box 486, Ellinwood, Kansas 67526
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed April 19 1972
Application for plugging approved April 20 1972
Plugging commenced April 24 1972
Plugging completed May 8 1972
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3865 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	987'	8 5/8"	987'	none
		0	3865'	5 1/2"	3865'	2139.31

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 2980' and dumped 5 sacks of cement.

Set rock bridge at 375'. Plugged well with 5 yards of ready mix cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1972
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of May, 1972

My commission expires Feb. 10, 1975
George A. Meyer Notary Public.

15.145.01467.0000

W. K. BELL 3

CENTER NE SW NE SECTION 27-21S-16W
PAWNEE COUNTY, KANSAS
GULF OIL CORPORATION

13-3/8" O. D. Casing cemented at 97'
8-5/8" O. D. Casing cemented at 987'
5-1/2" O. D. Casing cemented at 3865'

Drilling Commenced 6-27-53
Drilling Completed 7-12-53

FROM	TO	FORMATION	REMARKS
0'	97'	Sand	13-3/8" O. D. casing cemented with 100 sacks Portland cement at 97'
97	380	Red bed & shale	
380	400	Shale & shells	
400	515	Sand	8-5/8" O. D. casing cemented at 987'
515	665	Shale	
665	970	Shale & shells	
970	987	Red bed & anhydrite	
987	1017	Anhydrite	
1017	1340	Shale & shells	
1340	1550	Salt, shale & shells	
1550	1900	Shale & shells	
1900	2015	Shale & lime	
2015	2200	Lime	
2200	2230	Shale & lime	5-1/2" O. D. casing cemented with 100 sacks cement at 3865'
2230	2510	Lime & shale	
2510	2705	Shale & lime	
2705	2835	Shale	
2835	3105	Shale & lime	
3105	3440	Lime	
3440	3510	Shale & lime	
3510	3805	Lime	
3805	3860	Simpson shale	
3860	3862	Sand	
3862	3865	Lime	
T. D.	3865'		

RECEIVED
STATE CORPORATION COMMISSION
APR 20 1972
CONSERVATION DIVISION
Wichita, Kansas