

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.145.00918.0000

API NUMBER Dilled 4-54

LEASE NAME Miles

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div. NE NW SE Ft. from S Section Line
_____ Ft. from E Section Line

LEASE OPERATOR Champlin Petroleum Co.

SEC. 27 TWP. 21 SRGE. 16W (E) or (W)

ADDRESS 6441 NW Grand Blvd. Suite 300 Okla. City, Okla.

COUNTY Pawnee

PHONE#(405) 840-5521 OPERATORS LICENSE NO. 6417

Date Well Completed 4-24-84

Character of Well Oil

Plugging Commenced 11-20-84

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-23-84

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3868

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	995	none
				5 1/2	3890	2006
				2 3/8	3897.24	3897.24

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each

Pump 1 sk. of hull's & 25 sks. of cement @ 3872 to 3672

Pump 25 sks. of cement @ 1040

Pump 25 sks. of cement @ 520

Put 10 sks. of cement @ 40 to 0 Cut off & cap 3' below ground level

(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1984

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6347

Address Box 506 Liberal, Kansas 67901

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Marilyn Day (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Marilyn Day

(Address) 6441 N. W. Grand, Okla City, Ok

73116

SUBSCRIBED AND SWORN TO before me this 19th day of December, 19 84

[Signature]
Notary Public

My Commission Expires: 10-8-87

Form CP-4
Revised 08-84

RECEIVED DEC 8 1984


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. CHAMPLIN REFINING CO.
Farm. Miles No. 3

SEC. 27 T. 21 R. 16W
NE NW SE
2310' fr SL, 1650' fr EL, SE/4

Total Depth. 3870
Comm. 4-8-54 Comp. 4-24-54
Shot or Treated.
Contractor,
Issued. 6-19-54

County Pawnee
KANSAS



CASING:
8 5/8 995.74' w/ 500 sx cmt.
5 1/2 3890.38' w/ 125 sx cmt.
2 1/2 3897.24'

Elevation. 1991

Production. 341 BO / 1% water

Figures indicate Bottom of Formations.

shale & sand	300
sand & red bed	982
red bed & lime	1210
shale & sand	1908
shale, sand & lime	2090
shale & lime	2240
shale, sand & lime	2326
shale & lime	3108
lime	3374
shale & lime	3434
lime	3494
shale & lime	3609
lime & sand	3640
lime	3737
shale & lime	3870
Total Depth	

TOPS:
Heebner 3398
Brown lime 3489
Base KC 3499
Conglomerate 3737
Arbuckle 3867

15.145.00918.0000

TO WICHITA CORPORATION COMMISSION
 OFFICE OF THE CLERK OF
 THE PUBLIC UTILITIES
 WICHITA, KANSAS

COUNTY Pawnee

SUC. 27 TWP. 21S RGE. 16W

COMPANY OPERATING Champlin Refining Company

OFFICE ADDRESS Box 552 - Enid, Oklahoma

WELL NAME Miloo WELL NO. 3

WELL LOCATED NE 1/4 NW 1/4 SE 1/4 of Section 27-21S-16W or
2310' from South line and 1650' from East line of SE 1/4

CHARACTER OF WELL Oil

DRILLING COMMENCED April 6, 1954

DRILLING COMPLETED April 24, 1954

SIZE	WEIGHT	THDS	MARK	FT.	AMOUNT PULLED	CEMENT
8-5/8"	32#	8 Rd	National	225.74		500 Sacks
5-1/2"	11#	8 Rd	National	3,090.38		125 Sacks
2-1/2"	SUE 6.5#		National	3,097.24		

FORMATION RECORD

	TOPS	BOTTOM	TOPS	BOTTOM
Shale-Sand	0	300	Elevation: 702' K.B.	
Sand- Red Rod	300	982		
Red Rod-Line	982	1210		
Shale-Sand	1210	1908	Geological Tops:	
Shale-Sand-Limo	1908	2090	Heotnor	3398
Shale-Limo	2090	2240	Brown Line	3489
Shale-Sand-Line	2240	2326	Dase K.C.	3499
Shale-Line	2326	3108	Conglomerate	3737
Limo	3108	3374	Artucklo	3067
Shale-Limo	3374	3434		
Limo	3434	3494		
Shale-Line	3494	3609		
Limo-Sand	3609	3640		
Limo	3640	3737		
Shale-Line	3737	3870 T.D.		

RECEIVED
 STATE CORPORATION COMMISSION

09 1954

Superintendent

CONSERVATION DIVISION
 Wichita, Kansas

Notary Public

Filed for record and return to before me
 this 19th day of May, 1954

Witness my hand and seal this August 11, 1954