

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-145.00777.0000

LEASE NAME Cossmon

WELL NUMBER A 3

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 27 TWP. 21S RGE. 16W or (W)

COUNTY Pawnee

Date Well Completed         

Plugging Commenced 5-23-90

Plugging Completed 6-12-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Rt #3 Box 20-A Great Bend, Ks. 67530

PHONE#(316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filled?          If not, Is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3860'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	994'	none
				5 1/2"	3854'	2832'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.  
Sanded bottom to 3285' dumped 5 sacks cement. Shot pipe @3115', 2832'.  
Mixed 2 hulls, 8 gel, 50 sacks cement, 12 gel, 1 hull, blew hole in surface  
tried to patch hole had more holes. run 610' tubing. Tried to drill cement and  
couldn't Cleaned hole and cellar. Used 200 sks. 60/40 6% gel, 300# hulls, 5 sacks cement.  
(If additional description is necessary, use BACK of this form.) (Over)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Phillips Petroleum Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

RECEIVED  
STATE CORPORATION COMMISSION

6-22-90

SUBSCRIBED AND SWORN TO before me this 18 day of June, 19 90

CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires:         

IRENE HERZBERG  
State of Kansas  
My Appt. Exp. Aug. 24, 1993

Notary Public

Plugged with 12 sacks gel, 50 sacks cement @1050'. Pulled tubing to 330' and circulated cement to surface. 150 sacks 60/40 6% gel.