

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pan American Petroleum Corporation
 Complete Address: P. O. Box 432, Liberal, Kansas
 Lease Name H. Baier Well No. # 1
 Location NE SE NE Sec. 25 Twp. 21 Rge. 14 (E) (W)
 County Stafford Total Depth 4412'
 Abandoned Oil Well Gas Well Input Well SWD Well X D & A
 Other well as hereafter indicated:
 Plugging Contractor: Glen & Smith Casing Pulling Company
 Address: Box 156, Ellinwood, Kansas License No. 396
 Operation Completed: Hour 22:45PM Day 18th Month August Year 1965

The Above well was plugged as follows:

No record of any surface pipe. 3752' of 5½" long string, cemented with 85 sacks. Tubing had parted at 815', and 5½" casing had collapsed in the hole. Bridge was set on tubing at 815', and cemented with 2 sacks of Cal-Seal. 300' of 5½" long string was recovered from the hole. Fluid was up in the hole. Bridge plug was pushed to 250' in the 8 5/8" surface pipe, rock bridge from 250' to 240', 3 sacks of cement and 8% Calcium Chloride was mixed in barrel, and put on plug at 240', through the dump bailer, and let set for 2 hours. Hole was bailed dry, and 22 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 8/20/65
INV. NO. 1666-W