

15.185.00605.0000

Form CP-3  
Rev. 6-26-62

KP  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 22 1965  
4-22-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name William Cohen & Company

Complete Address: 245 Patton, Wichita, Kansas

Lease Name Russell "A" Well No. # 1

Location SW SE NW Sec. 25 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3772'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 2:00PM Day 21st Month April Year 1965

The Above well was plugged as follows:

209' of 8 5/8" surface pipe, cemented with 175 sacks. 3771' of 5 1/2" long  
string, cemented with 100 sacks. Top perforation 3522'. Plug was pushed  
to 3540', and 30' of sand, and cemented with 5 sacks. 3187' of 5 1/2" long  
string was recovered from the hole. Fluid was up in the hole. Bridge plug  
was pushed in fluid to 209', and 10' of rock bridge on plug. 3 sacks of  
cement with 8% Calcium Chloride was mixed in barrel and put on plug at  
200', through the dump bailer, and let set for 2 hours. Fluid in hole was  
bailed dry, and 22 sacks of cement was added to the plug. Hole was filled  
with mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the  
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/22/65

INV. NO. 1032-41