

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued December 13, 1967.

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dafga, Inc.

Complete Address: Victoria, Kansas 67671

Lease Name Wilson Well No. # E-1

Location NE SW NE Sec. 27 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3659'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 11:45AM Day 10th Month February Year 1968

The Above well was plugged as follows:

220' of 8 5/8" surface pipe, cement circulated. 3658' of 5 1/2" long string, cemented with 125 sacks. Plug back T.D. 3618'. Top perferation 3507'. Bottom of the hole was sanded to 3475', and cemented with 5 sacks, through the dump bailer, with cement from 3475' to 3435'. 2100' of 5 1/2" long string was recovered from the hole. Surface pipe was egged, and could not be swaged. A steel plate with a 2" collar was welded on the top of the surface pipe. 10 sacks of Gel-Mud and 80 sacks of cement was punped in to the surface pipe, through the 2" collar, to a pressure of 100 lbs., with cement from 240' to the top of the surface pipe, A 2" bull plug was screwed in the collar of the steel plate.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 2/13/68
INV. NO. 7257-W