


 KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued December 13, 1967.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 29 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Dafga, Inc.

Complete Address: Victoria, Kansas 67671

Lease Name Wilson Well No. # 1

Location NE NE NE Sec. 27 Twp. 21 Rge. 12 (E)     (W) W

County Stafford Total Depth 3685'

Abandoned Oil Well X Gas Well     Input Well     SWD Well     D & A    

Other well as hereafter indicated:    

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 4:15PM Day 26th Month January Year 1968

The Above well was plugged as follows:

307' of 8 5/8" surface pipe, cement circulated. 3682' of 4 1/2" long string,  
cemented with 125 sacks. Plug back T.D. 3577'. Top perferation 3046'. Bottom  
of the hole was sanded to 3000', and cemented with 4 sacks, through the dump  
bailer, with cement from 3000' to 2950'. 2000' of 4 1/2" long string was recover-  
ed from the hole. Bridge plug was pushed in fluid to 280', bridge plug and rock  
bridge from 280' to 270'. 7 sacks of cement and 6% Calcium Chloride was mixed  
was mixed in a barrel, and put on plug at 270', through the dump bailer, and  
let set for 4 hours. Hole was bailed dry, and 18 sacks of cement was added to  
the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and  
cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 1/29/68

INV. NO. 9165-W